

~~KANSAS~~

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-153-20185-00-00

RECEIVED
STATE CORPORATION COMMISSION

SEP 30 1974

CONSERVATION DIVISION
Wichita, Kansas

9-30-74

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Abercrombie Drilling, Incorporated,

Complete Address 801 Union Center, Wichita, Kansas.

Lease Name Myers Well No. 1

Location 150' SE of CNW-NE Sec. 35 Twp. 4 Rge. (E) (W) 34

County Rawlins Total Depth 4660'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 8:00 PM Day 25 Month 9 Year 1974

The above well was plugged as follows:

276'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1675'.

Circulated hole with heavy mud. Pulled DP to 1900' and displaced 110 Cu. Ft. cement
thru DP from 1900' to 1575'. Pulled DP to 280' and displaced 30 Cu. Ft. cement thru
DP from 280' to 205'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 10/1/74
INV. NO. 9990-W