

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

15-153-19013-00-00

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

SEP 9 1965  
9-9-65  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Eli Wilkerson,

Complete Address: 6520 Claytonia, Wichita, Kansas.

Lease Name Bowles Well No. 1

Location CSW-SW Sec. 24 Twp. 4 Rge. (E) (W) 34

County Rawlins Total Depth 4850

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Knight Casing Pulling Company,

Address: Box #405, Chase, Kansas. License No. 436

Operation Completed: Hour 2:00PM Day 4 Month 9 Year 1965

The Above well was plugged as follows:

295'--3 5/8" Surface pipe, cement circulated.  
4498'--5 1/2" Production casing cemented with 100 Sx. Top perforations @ 4206'

Pushed plug to 4100', sanded 30' and set 5 Sx. cement with dump bailer.  
Pulled 5 1/2", set bridging plug @ 500' and filled hole to within 10' of  
bottom of cellar with 6 1/2 yards Redi-Mix. Capped off hole with 2 Sx.  
sack cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. L. Nichols  
Well Plugging Supervisor

DATE 9/10/65  
INV. NO. 1984-W