

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
211 NORTH BROADWAY
WICHITA, KANSAS

WELL PLUGGING APPLICATION FORM
File One Copy

15-039-19008-0000

Lease Owner Peel-Hardman Oil Operators Address R. R. #3, Box 144B, Wichita, Kansas
(Applicant)

Lease (Farm Name) Nellans Estate Well No. 1

Well Location SE NE SE Sec. 26 Twp. 4S Rge. (E) 27 (W)

County Decatur Field Name (if any) _____

Total Depth 3542 Oil _____ Gas _____ Dry Hole x

Was well log filed with application? Yes If not, explain: _____

Date and hour plugging is desired to begin 8:00 A. M. 10-2-56

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission.

Name of the person on the lease in charge of well for owner Roy Eckel

Address Hill City, Kansas

Plugging Contractor Bert Self

Plugging Contractor's License No. _____

Address R. R. #4, Hutchinson, Kansas

Invoice covering assessment for plugging this well should be sent to Peel-Hardman

Oil Operators Address R. R. #3, Box 144B, Wichita, Kansas

and payment will be guaranteed by applicant.

PLUGGING
FILE SEC 26 T. 4 R. 27W
BOOK PAGE 104 LINE 19

Roy Eckel
Applicant or Acting Agent

Date October 2, 1956.

RECEIVED
STATE CORPORATION COMMISSION

OCT 4 X 1956

10-4-56

CONSERVATION DIVISION
Wichita, Kansas

DRILLERS' LOG

Company: Peel-Hardman Oil Operators

SE NE SE
Sec. 26, Twp. 4S, Rge. 27W,

Farm Name: Nellens Well No. 1

County: Decatur,
Kansas

Total Depth: 3525'

Comm: 8/29/56 Comp: 9/6/56
Contractor: Peel Brothers, Inc.

Elevation:

Production:

Casing: 8 5/8" @ 262 1/2' cem.
5 1/2" @ 3524' cem.

Figures below indicate bottoms of formations:

Surface clay	0 -	40
Sand		75
Sand and shale		263
Blue gray shale		490
White lime		550
Shale		900
Sand		930
Shale and shells		1320
Sand		1350
Shale and shells		1590
Shale		2005
Anhydrite		2045
Shale		2060
Shale and shells		2480
Shale and lime		2795
Broken lime and shale		2905
Shale and lime		2982
Shale, lime and pyrite		3095
Lime and shale		3170
Lime		3186
Lime and shale		3245
Lime		3430
Lime and shale		3490
Lime		3525
Total Depth		3525

This is to certify that the above information is to the best of our knowledge, true and correct.

PEEL BROTHERS, INC.

BY: Al H. Smith

SUBSCRIBED AND SWORN to before me this 14th day of September, 1956

My commission expires: April 27, 1960

Ruth Brant
Notary Public

Moved in Cable Tools 9-10-56 and deepened to 3542 9-11-56. Perf. from 3496-3540, tested w/ bailer 64 gals. fluid in 1 hr. with slight show of oil. Perf. on 9-12-56 24 shots from 3454-3460 and acidized w/1000 gals. Swabbed. Acidized w/2000 gals and swab tested. Perf. on 9-13-56 w/21 shots from 3180-87, acidized w/1000 gal. & swab tested. Swab tested on 9-14-56 and squeezed perforations. Waited on cement on 9-15-56 and 9-16-56. Drilled cement on 9-17-56 and Perf. w/25 shots from 3180-87. Acidized w/1500 gals. Swab tested. Perf on 9-18-56 and acidized w/5000 gals. Perf. 9-19-56 w/20 shots from 3170-74, no increase; Perf. w/20 shots from 3150-58, no increase; Perf. w/5 shots from 3132-34 and 5 shots from 3117-19; swabbed water with very small show of oil. Completed as a dry hole on 9-20-56.

PLUGGING
FILE SEC 26 T 4 R 27W
BOOK PAGE 104 LINE 19

RECEIVED
STATE CORPORATION COMMISSION
OCT 4 X 1956
CONSERVATION DIVISION
Wichita, Kansas



15-039-19008-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
211 NORTH BROADWAY
WICHITA, KANSAS

October 2, 1956

Well No. 1
Lease Hollans
Description SW NE SE 26-1-27W
County Decatur
File No. 10b-19

Paul-Hardman Oil Operators
R. R. # 3, Box 144
Wichita, Kansas

Gentlemen:

This letter is your authority to plug the above subject well, in accordance with the Rules and Regulations of the State Corporation Commission. When you are ready to plug this well, please contact our District Plugging Supervisor, Mr. Eldon Petty, Box 326, Hays, Kansas.

STATE CORPORATION COMMISSION
CONSERVATION DIVISION

By S. S. Greider
S. S. Greider
WELL PLUGGING SUPERVISOR

cc:
District Plugging Supervisor