

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
245 North Water
WICHITA, KANSAS 67202

Rev. 6-3-74
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

API Number 15-153-20336-0000 (of this well)
Lease Owner Moble C. Hoover
Address 302 NBC Building, El Dorado, Arkansas 71730
Lease (Farm Name) Gene Samson Well No. 1
Well Location SE NE Sec. 25 Twp. 4S Rge. 33W (E) (W) X
County Rawlins Total Depth 4650' Field Name
Oil Well Gas Well Input Well SWD Well Rotary D & A X
Well Log attached with this application as required Yes
Date and hour plugging is desired to begin 12:15 p.m., 12-28-78

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Gerrell Veatch Address Friendly Acres, Lot #73, Colby, KS

Plugging Contractor Abercrombie Drilling, Inc. License No.

Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to:

Name Moble C. Hoover

Address 302 NBC Building, El Dorado, Arkansas 71730

and payment will be guaranteed by applicant or acting agent.

Signed: *Jack L. Partridge*
Applicant or Acting Agent

Jack L. Partridge
Date: January 9, 1979

RECEIVED
JAN 10 1979
1-10-79

CONTRACTOR'S WELL LOG

OPERATOR: Moble C. Hoover
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: Gene Samson #1
 LOCATION: SE NE, Section 25-4S-33W
 Rawlins County, Kansas
 SPUD DATE: December 16, 1978
 COMPLETION DATE: December 28, 1978

0	247	Clay, sand & shale
247	1587	Shale & sand
1587	2110	Shale
2110	2311	Sand & shale
2311	2515	Shale & sand
2515	2770	Shale
2770	2809	Anhydrite
2809	3245	Shale
3245	3815	Shale & lime
3815	4010	Lime & shale
4010	4055	Lime
4055	4110	Lime & shale
4110	4650	Lime
	4650	Rotary Total Depth

Spud hole at 6:30 p.m., December 16, 1978. Drilled 247' of 12 1/4" hole. Ran 6 joints of 8 5/8" - 28# used surface casing. Set at 246' K.B. with 190 sacks of 60/40 posmix, 3% Ca.Cl., 2% gel. Plug was down at 12:00 midnite on December 16, 1978.

T.D. 4650'. Set 1st plug at 1800' with 70 sacks, 2nd plug at 240' with 20 sacks, 3rd plug at 40' solid bridge with 10 sacks, rathole with 5 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 12:15 p.m., December 28, 1978.

SAMPLE TOPS:

Anhydrite 2770'
 B/Anhydrite 2809'

RECORDED
 STATE COMMISSIONER
 JAN 20 1979
 1-10-79

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Gene Samson #1, SE NE, Section 25-4S-33W, Rawlins County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
 Jack L. Partridge
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 9th day of January, 1979.



Sherrie L. Brooks
 Sherrie Brooks, Notary Public

My commission expires 8-21-82.



15-153-20336-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

January 3, 1979

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Gene Samson
Description	SE NE Sec. 25-4-33W
County	Rawlins
Total Depth	4650
Plugging Contractor	Abercrombie Drilling, Inc.


Moble C. Hoover
NBC Plaza, Suite 302
El Dorado, Arkansas 71730

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,


J. Lewis Brock, Administrator

Mr. ~~Gilbert Balthazor, P.O. Box 9, Route #1, Palco, Kansas 67657~~
is hereby assigned to supervise the plugging of the above
named well.