

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
245 North Water
WICHITA, KANSAS 67202

Rev. 6-3-74
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

API Number 15 - 193 - 20362 - 0000 (of this well)
Lease Owner Moble C. Hoover
Address 302 NBC Building El Dorado, Arkansas 71730
Lease (Farm Name) George Franklin Well No. 1
Well Location C NE NE Sec. 22 Twp. 4S Rge. 33W (E) (W)X
County Rawlins Total Depth 4380' Field Name _____
Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ Rotary D & A X
Well Log attached with this application as required Yes
Date and hour plugging is desired to begin 8:30 p.m., 01-13-80

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Gerrell Veatch Address 1207 Court Place, Colby, Kansas

Plugging Contractor Abercrombie Drilling, Inc. License No. _____

Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to: **RECEIVED**
STATE CORPORATION COMMISSION

Name Moble C. Hoover

Address 302 NBC Building, El Dorado, Arkansas 71730 **JAN 17 1980**

and payment will be guaranteed by applicant or acting agent.

CONSERVATION DIVISION
Wichita, Kansas

1-17-80

Signed: Jack L. Partridge
Applicant or Acting Agent

Jack L. Partridge

Date: January 16, 1980

15-153-20362-0600

CONTRACTOR'S WELL LOG

OPERATOR: Moble C. Hoover
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: George Franklin #1
 LOCATION: C NE NE, Section 22-4S-33W
 Rawlins County, Kansas
 SPUD DATE: January 03, 1980
 COMPLETION DATE: January 13, 1980

0	85	Clay and sand
85	286	Sand and shale
286	2704	Shale and sand
2704	2730	Anhydrite
2730	2824	Shale
2824	3088	Lime and shale
3088	3330	Shale and lime
3330	3535	Shale
3535	3925	Lime and shale
3925	4198	Lime
4198	4330	Lime and shale
4330	4380	Lime
	4380	Rotary Total Depth

Spud hole at 9:30 p.m., January 03, 1980. Drilled 286' of 12 1/4" hole. Ran 7 joints of 8-5/8" new 20# casing. (Talley 278'). Set at 285' R.B. with 200 sacks of 60/40 posmix, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 4:00 a.m., January 04, 1980.

T.D. 4380'. Set 1st plug at 1700' with 70 sacks, 2nd plug at 280' with 20 sacks, 3rd plug at 40' solid bridge with 10 sacks, rathole with 5 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 8:30 p.m., January 13, 1980.

SAMPLE TOPS:
 Anhydrite 2704'
 B/Anhydrite 2730'

RECEIVED
 STATE CORPORATION COMMISSION
 1-17-80

JAN 17 1980

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

CONSERVATION DIVISION
 Wichita, Kansas

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the George Franklin #1, C NE NE, Section 22-4S-33W, Rawlins County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
 Jack L. Partridge
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 16th day of November, 1980.



Sherrie L. Brooks
 Sherrie Brooks, Notary Public

My commission expires 08-21-82.

State of Kansas



15-153-20362-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

JOHN CARLIN
R. C. LOUX
JANE T. ROY
WILLIAM G. GRAY
Carol J. Larson, Executive Secretary

Governor
Chairman
Commissioner
Commissioner

January 21, 1980

WELL PLUGGING AUTHORITY

Franklin Well No. 1
C NE NE, Sec. 2204S-33W
Rawlins County
4380'
Abercrombie Drlg., Inc.


Moble C. Hoover &
Abercrombie Drilling
302 NBC Bldg.
El Dorado, Arkansas 71730

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after ninety (90) day from the above date.

Yours very truly,


J. LEWIS BROCK, Administrator

Mr. Gilbert Balthazor, Box 9, Palco, KS 67657
is hereby assigned to supervise the plugging of the above named well