

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
500 INSURANCE BUILDING
212 NORTH MARKET
WICHITA 2, KANSAS

RECEIVED
STATE CORPORATION COMMISSION
MAR 5 1962
3-5-62
CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING APPLICATION FORM
File One Copy

Lease Owner (Applicant) HARMS-BURT DRILLING COMPANY 15-153-30150-00-00
Address P.O. BOX 488 Great Bend, Kansas
Lease (Farm Name) Davis Well No. 1
Well Location NW NW NW Sec. 4 Twp. 4 Rge. 33 (E) (W) W
County Rawlins Field Name (if any) Wildcat
Total Depth 4704 Oil Well Gas Well Input Well SWD Well D & A D&A
Was well log filed with application? Yes If not, explain:

Date and hour plugging is desired to begin February 25, 1962
Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission.

Name of person on the lease in charge of well for owner Doyle Rand
Address P.O. Box 488 Great Bend, Kansas

Plugging Contractor Harms Drilling Company License No.
Address P.O. Box 488 Great Bend, Kansas

Invoice covering assessment for plugging this well should be sent to Harms Drilling Company
Address P.O. Box 488 Great Bend, Kansas

and payment will be guaranteed by applicant.

Signed: *Alfred S. ...*
Applicant or Acting Agent

Date: February 25, 1962

D R I L L E R S L O G

Company: Harms-Burt Drilling Company
 Farm: Davis # 1
 Commenced: February 13, 1962
 Elevation: 3104 KB

NW NW NW Section 4-4-33W
 Rawlins County, Kansas
 Completed: February 25, 1962

0 - 190 shale
 190 - 215 sand
 215 - 1100 shale
 1100 - 2350 shale & sand streaks
 2350 - 2460 shale-shells
 2460 - 2560 shale-sand
 2560 - 2605 anhydrite
 2605 - 2700 red bed
 2700 - 2960 shale-shells
 2960 - 3170 shale-lime
 3170 - 3435 lime-shale
 3435 - 3770 shale-lime
 3770 - 4010 lime
 4010 - 4014 Heebner
 4014 - 4660 lime
 4660 - 4685 conglomerate
 4685 - 4704 chert
 4704 Total Depth

Set 274' of 8 5/8 inch surface pipe. Cemented with 175 sacks of common cement with 2% calcium chloride.

Tops: Anhydrite - 2560'
 Heebner - 4010'
 Lansing - 4050'
 Marmaton - 4284'
 Cherokee - 4472'
 Mississippi - 4685'

Drill Stem Tests: #1 4042 - 4085 Open 1 hour. Shut in 20 minutes. Recovered 190' muddy salt water. IBHP - 1240# FBHP - 1185# IFP - 145# FFP - 180#
 #2 4096 - 4157 Open 1 hour. Shut in 20 minutes. Recovered 42' slightly oil specked mu. IBHP - 990# FBHP - 175# IFP - 145# FFP - 165#


Ran electric log.

Dry, plugged, and abandoned.


A F F I D A V I T

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

I, Allan Harms of the Harms-Burt Drilling Company being first duly sworn on oath state: I have knowledge of the facts, statements and matters herein contained and the same are true and correct.


 Allan Harms

Subscribed and sworn to before me this 27th day of February, 1962.


 Notary Public Helen E. Gearhart

My commission expires January 22, 1966.



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

RECEIVED
STATE CORPORATION COMMISSION

FEB 23 1962
2-28-62
CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING AUTHORITY

Harms & Burt
 Box 184
 Great Bend, Kans

Well No. 1
 Lease Davis
 Description NW NW NW 4-4-35
 County Rawlins

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Very truly yours,

J.P. Roberts
 J. P. ROBERTS
 Assistant Petroleum Conservation
 Director

Mr. Eldon Petty
 is hereby assigned to supervise the plugging of the above
 named well.

In the event you need any further information regarding this well, feel free to write or call me at any time.

Harold J. Hollis
 Kansas Field Supervisor
 P. O. Box 85
 Great Bend, Kansas
 Phone: GL 3-2126