

KANSAS

Form CP-3  
Rev. 6-4-68

*Y* STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

15-023-20007-00-00

RECEIVED  
STATE CORPORATION COMMISSION

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

APR 9 1973  
4-9-73  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Pickrell Drilling Company,

Complete Address 705 Fourth National Bank Building, Wichita, Kansas.

Lease Name Carter Farms Well No. A-1

Location CSE-NW Sec. 36 Twp. 4 Rge. (E) (W) 37

County Cheyenne Total Depth 4765'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Above

Address      License No.     

Operation Completed: Hour 3:15 PM Day 5 Month 4 Year 1973

The above well was plugged as follows:

330'--8 5/8" Surface casing, cement circulated with 190 Sx.  
Top of Dakota section @ 2000'.

Circulated hole with heavy mud. Pulled DP to 2225' and displaced 110 Cu. Ft. cement  
thru DP from 2225' to 1900'. Pulled DP to 340' and displaced 30 Cu. Ft. cement thru DP  
from 340' to 265'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement  
to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *W. L. Nichols*  
Well Plugging Supervisor

DATE 4/10/73  
INV. NO. 9223-4