

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

15-153-30157-00-00

AUG 28 1963
8-28-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Empire Drilling Company,
Complete Address: 650 Fourth National Bank Bldg., Wichita, Kansas.
Lease Name Williams Ranch Well No. 1
Location CSE-NW Sec. 11 Twp. 4 Rge. (E) (W) 36
County Rawlins Total Depth 4860'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: Above
Address: License No.
Operation Completed: Hour 9:30PM Day 24 Month 8 Year 1963

The Above well was plugged as follows:

295'--8 5/8" Surface ~~ipe~~ pipe, cement circulated.
Circulated hole with heavy mud, set plug @ 600' and displaced 20 Sx
cement thru DP. Heavy mud to 280', set plug with 1/4 sack hulls and 20
Sx. cement displaced thru DP. Heavy mud to 30', set plug with 1/2 Sk.
hulls and 10 Sx cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 8/28/63
INV. NO. 9661-w

Signed: H. L. Nichols
Well Plugging Supervisor