

*96*  
 KANSAS  
 STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-023-30042-00-00

RECEIVED  
 STATE CORPORATION COMMISSION

APR 8 1963  
 4-8-63  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. F. Roberts  
 Assitant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Operator's Full Name Toto Gas Co.,

Complete Address: 7400 St., Zone 12, Oklahoma City, Oklahoma.

Lease Name Rubin Reuber Well No. 1

Location CNW-NE Sec. 36 Twp. 4 Rge. (E) (W) 37

County Cheyenne Total Depth 4527

Abandoned Oil Well x Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Co.,

Address: Box #221, Great Bend, Kansas. License No. 49

Operation Completed: Hour 1:00PM Day 4 Month 4 Year 1963

The Above well was plugged as follows:

304' 8 5/8" surface pipe , cement circulated w/200 Sx.  
4 1/2" set @ 4471', cemented w/150 Sx. Top of perforations @ 4445'.  
Sanded well back to 4435' and set 5 Sx cement w/dump bailer. Pulled  
4 1/2" to 600', circulated heavy gel mud(30 Sx) and displaced 20 Sx  
cement thru 4 1/2". Pulled 4 1/2" to 300', set plug and displaced 20 Sx  
cement thru 4 1/2". Pulled 4 1/2", set bridge @ 30' and 10 Sx cement to  
bottom of cellar. (Recovered 2000' 4 1/2" casing)  
(Mudding & cementing operations by Halliburton Oil Well Cementing Co.)

I hereby certify that the above well was plugged as herein stated.

**INVOICED**  
 DATE 4/8/63  
 INV. NO. 6854-W

Signed: N. L. Dickels  
 Well Plugging Supervisor