

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15039-20054-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 5 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name C & G Drilling Company,

Complete Address: 1107 Union National Building, Wichita, Kansas.

Lease Name Fringer Well No. 3

Location SE-NW-SE Sec. 8 Twp. 4 Rge. (E) (W) 28

County Decatur Total Depth 4100

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Above

Address: \_\_\_\_\_ License No. \_\_\_\_\_

Operation Completed: Hour 3:00 AM Day 31 Month 7 Year 1968

The Above well was plugged as follows:

244'--8 5/8" Surface casing, cement circulated with 190 Sx.

Circulated hole with heavy mud. Pulled DP to 1680' and displaced 100 Sx. cement thru

DP from 1680' to 1360'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from

275' to 215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement from

40' to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: N. L. J. [Signature]  
Well Plugging Supervisor

INVOICED

DATE 8/5/68

INV. NO. 8226-11