

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 22 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-039-20227-00-00

Operator's Full Name C & G Drilling Company,

Complete Address 1107 Union National Bank Building, Wichita, Kansas.

Lease Name Bishop Well No. 3

Location ^{NW} NE-NW-SW Sec. 8 Twp. 4 Rge. (E) (W) 28

County Decatur Total Depth 4130'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 4:00 PM Day 20 Month 3 Year 1972

The above well was plugged as follows:

274'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1450'.

Circulated hole with heavy mud. Pulled DP to 1675' and displaced 110 Cu. Ft. cement
thru DP from 1675' to 1350'. Pulled DP to 310' and displaced 30 Cu. Ft. cement thru
DP from 310' to 265'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *A. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 3/24/72
INV. NO. 5405-42