

KANSAS

*W*  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 26 1972  
06-26-1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-039-20122-00-00

Operator's Full Name C & G Drilling Company,  
Complete Address 1107 Union National Bank Building, Wichita, Kansas.  
Lease Name Bishop Well No. 2  
Location NE-SW-SW Sec. 8 Twp. 4 Rge. (E) (W) 28  
County Decatur Total Depth 4130'  
Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Rockhold Engineering, Incorporated,  
Address Box #698, Great Bend, Kansas. License No. 670  
Operation Completed: Hour 3:00 PM Day 16 Month 6 Year 1972

The above well was plugged as follows:

2111'--8 5/8" Surface casing, cement circulated with 200 Sx.  
4129'--5 1/2" Production casing cemented on bottom with 150 Sx. Top of perforations @ 3921'.  
Sanded well back to 3900' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing and squeezed well initially with 5 sacks hulls and 9 sacks gel and followed with 110 Cu. Ft. cement from 1675' to 1350' then 27 sacks gel from 1350' to 275' and followed with 30 Cu. Ft. cement from 275' to 200' then 4 sacks gel from 200' to 40' and finally 10 Cu. Ft. cement from 40' to bottom of cellar. Maximum pump-in pressure--700#.  
Final shut-in pressure--500#. (Mudding and cementing operations by Globe Cementing).

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Nichols*  
Well Plugging Supervisor

INVOICED

DATE 6/29/72  
INV. NO. 5930-W