

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
**Type or Print on this Form
Form must be Signed
All blanks must be Filled**

Lease Operator: VESS OIL CORPORATION
 Address: 8100 E. 22nd St. N., Bldg. 300, Wichita, KS 67226
 Phone: (316) 682-1537 Operator License #: 5030
 Type of Well: oil Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: _____ (Date)
 by: _____ (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
Topeka Depth to Top: 2894 Bottom: 3171 T.D. _____
LKC Depth to Top: 3216 Bottom: 3304 T.D. 3547
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-051-05016-00-00
 Lease Name: Gish C
 Well Number: 1
 Spot Location (QQQQ): _____ - NW - NW - NE
330' Feet from North / South Section Line
2310' Feet from East / West Section Line
 Sec. 2 Twp. 11S S. R. 16W East West
 County: Ellis
 Date Well Completed: 12/30/98
 Plugging Commenced: 10/5/04
 Plugging Completed: 10/6/04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	249'	none
				4-1/2"	3547'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

10/5/04-Perf'd @ 825' and 1270'. 10/6/04-TIH w/tbg to 1998'. Spotted 75 sx cement w/300# hulls.
Pulled tbg to 990' and circulated cement to surface w/40 sx cement . TOH.
Connected to 8-5/8" and pumped 25 sx SIP - 200#. Connected to 4-1/2" and pumped 20 sx - 800#.
SIP - 100#. Cement was 60/40 poz w/10% gel. Approved by Dennis Hamel w/KCC.

Name of Plugging Contractor: Allied Cementing Co., Inc. License #: 99996
 Address: P.O. Box 31, Russell, KS 67665-0031

Name of Party Responsible for Plugging Fees: Vess Oil Corporation
 State of Kansas County, Sedgwick, ss.


Pat Canaday (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) _____
 (Address) 8100 E. 22nd Street North, Bldg. 300, Wichita, KS 67226

SUBSCRIBED and SWORN TO before me this 15th day of October, 2004

Michelle D. Henning
 Notary Public

My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas - 67202

**RECEIVED
OCT 25 2004
KCC WICHITA**

ban

ALLIED CEMENTING CO., INC.

18764

Federal Tax I.D.# XXXXXXXXXX

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: R

DATE <u>10-6-04</u>	SEC.	TWP.	RANGE	CALLED OUT	ON LOCATION <u>9:00am</u>	JOB START <u>9:15am</u>	JOB FINISH <u>11:00am</u>
LEASE <u>Gish</u>	WELL # <u>C-1</u>	LOCATION <u>Natoma NW 5 S 1/4 E</u>		COUNTY <u>Ellis</u>	STATE <u>K</u>		
OLD OR NEW (Circle one)				<u>YES</u>			

CONTRACTOR Fisher Well Service OWNER _____

TYPE OF JOB plug to abandon

HOLE SIZE _____ T.D. _____

CASING SIZE 4 1/2 DEPTH _____

TUBING SIZE 2" DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

CEMENT			
AMOUNT ORDERED	<u>225 60</u>	<u>10/09/04</u>	
<u>5 Halls</u>			
<u>used 165</u>			
COMMON	<u>99</u>	@ <u>7.85</u>	<u>777.15</u>
POZMIX	<u>66</u>	@ <u>4.10</u>	<u>270.60</u>
GEL	<u>13</u>	@ <u>11.00</u>	<u>143.00</u>
CHLORIDE		@	
ASC		@	
<u>Halls</u>	<u>5</u>	@ <u>20.00</u>	<u>100.00</u>
HANDLING	<u>248</u>	@ <u>1.35</u>	<u>334.80</u>
MILEAGE	<u>59/SK/MILE</u>		<u>396.00</u>
TOTAL			<u>2022.30</u>

EQUIPMENT

345 Driver

PUMP TRUCK CEMENTER Steve

_____ HELPER _____

BULK TRUCK

_____ DRIVER _____

BULK TRUCK

213 DRIVER Rufus

REMARKS:

Ran tubin to 2000'
spot 25 sk w/ 3 Halls
pulled to 1000' spot
140 sk + 2 Halls + cir
cement, pulled tubin tied
on to 142 mixed 25 sk
pressured to 800 PSI shot in @ 2000psi
tied on to 8 1/2 mixed 25 sk
shot in @ 2000psi

CHARGE TO: Vess O&P

STREET _____

CITY _____ STATE _____ ZIP _____

RECEIVED
OCT 25 2004
KCC WICHITA

SERVICE

DEPTH OF JOB			
PUMP TRUCK CHARGE			<u>525.00</u>
EXTRA FOOTAGE		@	
MILEAGE	<u>32</u>	@ <u>4.00</u>	<u>128.00</u>
MANIFOLD		@	
		@	
		@	
TOTAL			<u>653.00</u>

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE [Signature]

PLUG & FLOAT EQUIPMENT

	@		
	@		
	@		
	@		
	@		
TOTAL			<u>2549.6</u>
TAX			
TOTAL CHARGE			
DISCOUNT			IF PAID IN 30 DAY

PRINTED NAME _____