

STATE OF KANSAS  
STATE CORPORATION  
COMMISSION  
130 South Market Room 2078  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R. 82-3-117

API NUMBER 15-007-228060000

LEASE NAME Ricke F *KCC  
BEM  
10-25-04*

WELL NUMBER F2  
460 Ft. from (N) S Section Line

1370 Ft. from (E) W Section Line

RECEIVED

OCT 25 2004

KCC WICHITA

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 60 days.

LEASE OPERATOR Woolsey Petroleum Company

SEC. 31 TWP. 33S RGE. 13 (E) or (W)

ADDRESS P.O. Box 198, Medicine Lodge, KS 67014

COUNTY Barber

PHONE # 620-886-5606 OPERATOR'S LICENSE NO. 33168

Date Well Completed \_\_\_\_\_

Character of Well good Dry Hole

Plugging Commenced 7/17/2004

(Oil, Gas, (D&A), SWD, Input, Water Supply Well)

Plugging Completed 7/19/2004

The plugging proposal was approved on 7/12/2004 (date)

by Steve Pfeifer (KCC District Agent's Name).

is ACO-1 filed? yes If not, is well log attached? yes

Producing Formation Cottonwood Depth to Top 2864 Bottom 2868 T. D. 2948

Show depth and thickness of all water, oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size   | Put in | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 10 3/4 | 231    | None       |
|           |         |      |    | 4 1/2  | 2948   | 2400       |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

7/19-set CIBP at 2840, dump 2 sacks portland with bailer, load casing, stretch and 4 1/2 at 2400

7/20-pull 4 1/2, run 2 3/8 tubing to 600', allied load hole with 10 sacks gel, spot 50 sacks cement, pull tubing to 250', spot 65 sacks cement, pull to 40', load to surface with 60/40 POZ, 6% jel, top with 30' sand

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105

Address P.O. Box 187, 107 W. Fowler, Medicine Lodge, KS 67104

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Woolsey Petroleum Company


STATE OF Kansas COUNTY of Barber, ss.

John Swinford (Employee of Operator) or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filled that the same are true and correct, so help me God.

(Signature) John Swinford

(Address) P.O. Box 187, Medicine Lodge, KS 67104

SUBSCRIBED AND SWORN TO before me this 21 day of October, 2004



Glenda Morrison  
Notary Public

My Commission Expires: November 30, 2006

*Bm*