

15-153-05150-00-00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Rawlins County, Sec. 23 Twp. 4S Rg. 24W (E) (W)  
Location as "NE/CNW/SW" or footage from lines 657 FSL and 659 FEL SE/4  
Lease Owner Phillips Petr. Co.  
Lease Name Reeves-A Well No. 1  
Office Address Box 287, Gt. Bend, Kan  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed August, 1959 19  
Application for plugging filed 8-14-67 19  
Application for plugging approved 8-15-67 19  
Plugging commenced 8-30-67 19  
Plugging completed 8-31-67 19  
Reason for abandonment of well or producing formation uneconomical

If a producing well is abandoned, date of last production July, 1967 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4612 Feet  
Show depth and thickness of all water, oil and gas formations. PTD 4493

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	RECEIVED STATE CORPORATION COMMISSION			8-5/8 4 1/2"	306 4547'	none 1748'
	SEP 7 1967					
	9-1-67					
	CONSERVATION DIVISION Wichita, Kansas					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

RU Knight csg pulling unit; worked casing; pumped Howco plug to 2965'. MP 1200#. plug stopped at 2965', pressure dropped to 500#. Shot 4 1/2 at 2934, 2738, 2535 and 2143.

Shot 4 1/2 at 1932 and 1745'. Pulled 53 jts (1748') of 4 1/2" OD 9.5#. Spotted 24 sx Jel followed with 80 sx cement from 1800 to 315'. Spotted 3 sx Jel, followed with 20 sx cement from 315 to 180', 3 sx Jel to 30', 5 sx cement to surface. Well P&A. 6p.m. 8-31-67.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Knight Casing Pulling Co.  
Address Chase, Kan

STATE OF Kansas, COUNTY OF Barton, ss.  
AT Slagle Dist. Supt. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A.T. Slagle  
Box 287, Gt. Bend, Kan  
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of SEPT. 1967

Lura Lee Parker  
Notary Public.

My commission expires 10-27-69

15-153-05150-00-00

EXPLORATION RECORD

Lease Reeves-A

Well 1

Formation Name	Top	Base	Remarks
Clay and sand	0	318	
Shale	318	2000	
Shale and sand	2000	2435	
Shale	2435	2485	
Lime	2485	2500	
Lime and shale	2500	2595	
Shale	2595	2815	
Anhydrite	2815	2845	
Shale	2845	2875	
Red Bed and Shale	2875	3175	
Shale	3175	3355	
Shale and lime	3355	3790	
Lime	3790	4360	
Lime and shale	4360	4404	
Lime	4404	4480	
Lime and shale	4480	4612	

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 7 1967  
CONSERVATION DIVISION  
Wichita, Kansas  
9-7-67