



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED STATE CORPORATION COMMISSION

JUL 23 1973

CONSERVATION DIVISION Wichita, Kansas

7-23-73

J. Lewis Brock Administrator 500 Insurance Building Wichita, Kansas 67202

Dear Sir:

Mr. L. C. Brau of E. K. Edmiston Drilling Co., Inc, this

date requested permission to plug the following described well:

Mr. Brau guarantees payment of the plugging fee.

Operator's full Name: Edmiston Oil Company,

Complete Address: 801 First National Bank Building, Wichita, Kansas.

Lease Name: Petrasek Well No. B-2

Location: NW-SE-SE Sec. 26 Twp. 4 Rge. (E)(W)27

County: Decatur Total Depth 3654' Oil Well

Gas Well Input Well BWD Well D & A X Lost Hole

Mr. Brau was instructed to plug the well as follows:

206'--8 5/8" Surface casing cemented on bottom with 200 Sx. Cement did not circulate. Cement circulated from top thru 1" with 100 Sx. Top of Dakota section @ 1100'.

Circulate hole with heavy mud. Pull DP to 1325' and displace 110 Cu. Ft. cement thru DP. Pull DP to 245' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

A. L. Nichols Conservation Division Agent