



15-039-20226-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 6 1972
CONSERVATION DIVISION
Wichita, Kansas
3-6-72

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. George Klein of Messman-Rinehart Oil Co., has this date requested permission to plug the following described well:

Mr. Klein guarantees payment of the plugging fee.

Operator's full Name: Messman-Rinehart Oil Company,

Complete Address: 1432 Wichita Plaza, Wichita, Kansas.

Lease Name: Petracek Well No. 3

Location: CNW-NE Sec. 26 Twp. 4 Rge. (E)(W) 27

County: Decatur Total Depth 3640' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Klein was instructed to plug the well as follows:

322'--8 5/8" Surface casing, cement circulated with 235 Sx.
Top of Dakota section @ 1025'.

Circulate hole with heavy mud. Pull DP to 1250' and displace 110 Cu. Ft. cement thru DP. Pull DP to 340' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

M. L. Nichols
Conservation Division Agent