



15-153-20148-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
FEB 26 1973
2-26-73
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. R. L. Sixbury of Murfin Drilling Company has this

date requested permission to plug the following described well:

Mr. Sixbury guarantees payment of the plugging fee.

Operator's full Name: Beacon Resources Corporation,

Complete Address: 1000 Century Plaza, Wichita, Kansas.

Lease Name: Chandler-Weber Well No. 1

Location: CNW-NW Sec. 23 Twp. 4 Rge. (E)(W) 35

County: Rawlins Total Depth 4734' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Sixbury was instructed to plug the well as follows:

289'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 1775'.

Circulate hole with heavy mud. Pull DP to 2000' and displace 110 Cu. Ft. cement thru DP. Pull DP to 310' and circulate 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent