

State of Kansas



15-153-20191-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED STATE CORPORATION COMMISSION

OCT 15 1974

CONSERVATION DIVISION Wichita, Kansas

10-15-74

J. Lewis Brock Administrator 500 Insurance Building Wichita, Kansas 67202

Dear Sir:

Mr. R. L. Sixbury of Murfin Drilling Company has this date requested permission to plug the following described well:

Mr. Sixbury guarantees payment of the plugging fee.

Operator's full Name: Zenith Drilling Corporation,

Complete Address: Suite 600, 200 W. Douglas, Wichita, Kansas.

Lease Name: Walters Well No. 1

Location: CNW-SE Sec. 17 Twp. 4 Rge. (E)(W) 33

County: Rawlins Total Depth 4460' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sixbury was instructed to plug the well as follows:

291'--8 5/8" Surface casing, cement circulated with 210 Sx. Top of Dakota section @ 1725'.

Circulate hole with heavy mud. Pull DP to 1950' and displace 110 Cu. Ft. cement thru DP. Pull DP to 310' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

Handwritten signature of A. L. Nichols

Conservation Division Agent