



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 5 1974
CONSERVATION DIVISION
Wichita, Kansas

3-5-74

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Albert Unruh of SW Casing Pulling Co., Inc. has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Beren Corporation.

Complete Address: 1130 Vickers KSB&T Building, Wichita, Kansas.

Lease Name: Walters Well No. 1

Location: NE-NE-SW Sec. 17 Twp. 4 Rge. (E)(W) 33

County: Rawlins Total Depth 4830' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

303'--8 5/8" Surface casing, cement circulated with 250 Sx.
4759'--5 1/2" Production casing cemented on bottom with 250 Sx. Top perforations from 4051' to 4081'. No plug back indicated.

Sand well back to 4025' and set 3 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 45 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

W. G. Nichols
Conservation Division Agent