



15153-20042-00-00

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 12 1969
 CONSERVATION DIVISION
 Wichita, Kansas
 6-12-69

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Ronnie Parks of Gabbert-Jones, Incorporated, has this date requested permission to plug the following described well:

Mr. Parks guarantees payment of the plugging fee.

Operator's full Name: Stonehenge Oil Company, Incorporated

Complete Address: 711 Franklin Building, Tulsa, Oklahoma

Lease Name: Mayfield Well No. 1

Location: NE-NE Sec. 10 Twp. 4 Rge. (E)(W) 35

County: Rawlins Total Depth 5110' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Parks was instructed to plug the well as follows:

302'--8 5/8" Surface casing, cement circulated with 275 Sx.
Top of Dakota section @ 1875'. Laid Owner requests surface pipe be left open. Well to be completed as a potential fresh water well.

open

Circulate hole with heavy mud. Pull DP to 1960' and displace 100 Sx.
cement thru DP. Pull DP to 335' and displace 20 Sx. cement thru DP. Pull DP,
set bridge @ 40' with 1/2 sack hyls and 10 Sx. cement to bottom of cellar.

Very truly yours,

A. L. Dehals
 Conservation Division Agent