

State of Kansas



15-153-20185-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

RECEIVED
STATE CORPORATION COMMISSION

SEP 30 1974

CONSERVATION DIVISION
Wichita, Kansas

9-30-74

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Don Favinger of Abercrombie Drilling, Inc., has this date requested permission to plug the following described well:

Mr. Favinger guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drilling, Incorporated,

Complete Address: 801 Union Center, Wichita, Kansas.

Lease Name: Myers Well No. 1

Location: 150' SE of CNW-NE Sec. 35 Twp. 4 Rge. (E)(W) 34

County: Rawlins Total Depth 4660' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Favinger was instructed to plug the well as follows:

276'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1675'.

Circulate hole with heavy mud. Pull DP to 1900' and displace 110 Cu. Ft. cement thru DP. Pull DP to 280' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

M. L. Nichols
Conservation Division Agent