



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

NOV 4 1965
11-4-65
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. John Woolley of Arvel C. Smith has this date requested permission to plug the following described well:

Mr. Woolley guarantees payment of the plugging fee.

Operator's full Name: Arvel C. Smith

Complete Address: 534 N. Tallyrand, Wichita, Kansas

Lease Name: Leebrick Well No. 1

Location: C NW SE Sec. 27 Twp. 4 Rge. 34 (X) (W)

County Rawlins Total Depth 4725 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Woolley was instructed to plug the well as follows:

8 5/8 surface pipe o. 289' circulated w/cement.
Mudded hole from 4725 feet to 700 feet. Set plug
& 20 sp cement. Mud to 300 feet; set plug and
20 sp cement. Hole mudded to 230 feet and
set fresh water bridge at request of landowner,

Very truly yours,

S. S. Greider
Conservation Division Agent



15-153-30154-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B HARVEY Secretary
E. EDWARD JOHNSON Gen Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

NOV 8 1965
11-8-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. John Woolley of Arvel Smith has this
date requested permission to plug the following described well:

Mr. Woolley guarantees payment of the plugging fee.

Operator's full Name: Arvel C Smith

Complete Address: 2809 Northwest Expressway - Okla City Okla.

Lease Name: Lebrick Well No. 1

Location: Nw-Se-1/4 Sec. 27 Twp. 4 Rge. 34 (E)(W)

County Raubens Total Depth 4725 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Woolley was instructed to plug the well as follows:

Jet pits circulate hole with heavy mud
set cement plug at 630' and displace 20 sac
cement, heavy mud to 250' set plug and
20 sac cement. Hole left open for water
well from that point

Very truly yours,

Gilbert P. Liker
Conservation Division Agent