

State of Kansas



15-153-19013-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 9 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Dwight Dellenger of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Eli Wilkerson Dellenger guarantees payment of the plugging fee.

Operator's full Name: Eli Wilkerson.

Complete Address: 6520 Claytonia, Wichita, Kansas.

Lease Name: Bowles Well No. 1

Location: CSW-SW Sec. 24 Twp. 4 Rge. (E)(W) 34

County Rawlins Total Depth 4850 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Dellenger was instructed to plug the well as follows:

295' --- 8 5/8" Surface pipe, cement circulated.
4498' --- 5 1/2" Production casing cemented with 100 Sx. Top perforations @4206.

Push plug to 4100, set 30' sand bridge and 5 Sx. cement with dump bailer. Pull pipe, set bridging plug @ 500' and fill hole with Redi-Mix cement.

Very truly yours,

A. L. Dill
Conservation Division Agent