

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Forest City LLC
 Address: 1201 Walnut - 14th Floor, Kansas City, MO 64106
 Phone: (816) 556-2972 Operator License #: 32877
 Type of Well: Gas well Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 10/15/2004 *KCC BEW 11-2-04 RBD MS - CP 2/3* (Date)
 by: Jack Robinson (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
None Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-013-20029-0000
 Lease Name: Oltjen
 Well Number: 1-2
 Spot Location (QQQQ): _____ - _____ - _____ - NENE
642 Feet from North / South Section Line
521 Feet from East / West Section Line
 Sec. 2 Twp. 3 S. R. 18 East West
 County: Brown
 Date Well Completed: na; reached TD on 12/13/2001
 Plugging Commenced: 10/19/2004
 Plugging Completed: 10/20/2004

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Not applicable -		Surface	23'	13 3/8"		none (see cut off below)
well never completed			250'	8 5/8"		none
			1995'	4 1/2"		none


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set 4 1/2" bolt bridge plug at 258' via wire line. Cut off casing stub. Mixed and pumped 30 sx Portland "A", 2% gel cement down tubing. Circulated cement to surface. Pulled out tubing. Topped off well, pumping it full to surface. Cut off casing approximately 4' below surface and backfilled.

Name of Plugging Contractor: Team Production Services, LLC License #: 33331
 Address: 1751 W. 49th, Chanute, KS 66720
 Name of Party Responsible for Plugging Fees: Forest City LLC
 State of _____ County, _____, ss.
David L. Henriksen
Vice President
 (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
 (Signature) [Signature] Vice President
 (Address) 1201 Walnut - 14th Floor, Kansas City, MO 64106

**RECEIVED
NOV 01 2004
KCC WICHITA**

SUBSCRIBED and SWORN TO before me this 27 day of October, 2004
[Signature] My Commission Expires: July 16, 2005
 Notary Public



KCC Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Bm