

API NUMBER 15-~~DK~~-20, 358-00-00 ⁰³⁹

LEASE NAME Bishop

WELL NUMBER 1-8

840 Ft. from S Section Line

990 Ft. from W Section Line

SEC. 8 TWP. 4S RGE. 28W (E) or (W)

COUNTY Decatur

Date Well Completed 11-21-76

Plugging Commenced 12-12-85

Plugging Completed 12-15-85

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Gemini Corporation

ADDRESS P.O. Box 309, McCook, Nebraska 69001

PHONE# (308) 345-2480 OPERATORS LICENSE NO. 6305

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays, Ks.

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Well drilled in 1976
Kansas City Depth to Top 3906 Bottom 4100 T.D. 4100

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				4 1/2"	4099'	2220'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Filled casing to 3360' with sand. Placed 4skts Class A Cmt on sand with Dump Bailer. Shot casing off at 2225KB and pulled. Hooked up to 8 5/8" csg. And mixed 8skts gel & 4skts hulls, 100skts 60-40 pozmix A 6% gel & 3% CC. over
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No.

Address Oberlin, Kansas

STATE OF Nebraska COUNTY OF Red Willow, ss.

Gerry W. Brown (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Gerry W. Brown

(Address) 204 N. Cherokee, McCook, NE 69001

SUBSCRIBED AND SWORN TO before me this 6th day of January, 19 86

Peggy J. Poore
 Peggy J. Poore Notary Public

My Commission Expires: 07-06-89



CONTRACTOR'S WELL LOG

15-039-20358-00-00

OPERATOR: GEMINI Corporation
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: BISHOP 1-8
 LOCATION: NE SW-SW Section 8-4S-28W
 Decatur County, Kansas
 SPUD DATE: September 20, 1976
 COMPLETION DATE: September 28, 1976

0	125	Surface clay
125	170	Sand
170	2571	Shade
2581	2603	Anhydrite
2603	3430	Shade
3430	3788	Shade and Lime
3788	3980	Lime and Shale
3980	4100	Lime
	4100	Rotary Total Depth

Spud at 6:15 p.m. 9-20-76. Drilled 204' of 12 1/4" hole, Ran 5 jts. of 8 5/8" casing (Tally 196'). Set at 203' K.B. with 180 sx. - 60/40 posmix, 3% Ca. Cl. Cement did circulate. Plug was down at 10:15 p.m. 9-20-76

Ran 129 jts. of 4 1/2" new and used casing. (Tally threads off - 4102.38') Set at 4099' K.B. Cemented with 100 sx. 50/50 posmix, 2% gel, 18% Salt, .75% CFR-2. Tailed with 55 sx. Class "A" cement, 1% latex. Plug was down at 4:00 p.m. 9-28-76.

SAMPLES TOPS:

Anhydrite 2571'
 B/Anhydrite 2603'

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jerry A. Langrehr, Executive Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the BISHOP 1-8, NE SW SW, Section 8-4S-28W, Decatur County, Kansas.

ABERCROMBIE DRILLING, INC.

By: Jerry A. Langrehr
 Jerry A. Langrehr, Exec. V. P.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 1st day of October, 1976.

Sandra Richman
 Sandra Richman, Notary Public



STATE BOARD OF PROFESSIONAL ENGINEERS AND SURVEYORS
 1980
 CONSERVATION DIVISION
 Wichita, Kansas

COPY