

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
500 INSURANCE BUILDING
212 NORTH MARKET
WICHITA, KANSAS 67202

FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

RECEIVED
STATE CORPORATION COMMISSION
10-20-69
OCT 20 1969
CONSERVATION DIVISION
Wichita, Kansas

Lease Owner TEXACO INC. 15-039-00480-0001
Address 614 Bitting Building, Wichita, Kansas 67202
Lease (Farm Name) R. L. Skubal "B" Well No. 1W
Well Location NE NE NE Sec. 35 Twp. 4S Rge. 27W (E) (W)
County Decatur Field Name (If Any) _____
Total Depth PBTD 3629 Oil Well _____ Gas Well _____ Input Well X SWD Well _____ D & A _____
Well Log filed with application ON FILE or Well Log filed with Plugging Supervisor _____
None available

Date and hour plugging is desired to begin 8:00 AM October 20, 1969

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission.

Name of company representative in charge of plugging operations Joel Lozano
111 West 8th Street Address Hays, Kansas

Plugging Contractor Texaco Inc. License No. _____
Address 614 Bitting Building, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to Texaco Inc.
614 Bitting Building Address Wichita, Kansas 67202

and payment will be guaranteed by applicant.

Signed: M. R. Wilson
Applicant or Acting Agent

Date: October 16, 1969


LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- NYE & SNELL DRILLING CO.
 Farm- Skubal No. 1

SEC. 35 T. 4 R. 27W
 NE NE NE

Total Depth. 3880
 Comin. 1-9-54 Comp. 1-21-54
 Shot or Treated.
 Contractor. Glenn R. Nye
 Issued. 2-13-54

County Decatur
 KANSAS



CASING:
 8 5/8" set at 525'

Elevation. 2565 R.B.

Production. Dry

Figures indicate Bottom of Formations

top soil and sand	155
sand & shale	290
sand & shale	380
shale	1085
shale & shells	1440
shale & sand	1710
shale & red bed	2070
anhydrite	2100
shale & red bed	2350
shale & shells	2520
lime & shale	3460
lime	3530
shale & lime	3852
granit wash	3880
Total Depth	

Tops: Scout	
Burlingame	3190
Lansing	3477
BKC	3648
Conglomerate	3816
Granite wash	3852

RECORDED
 OCT 14 1954
 10:30 AM

SUBSEQUENT OPERATION REPORT

Fulsa DIVISION

WELL Skubal "B" #1 DISTRICT Wichita
 AREA Hays FIELD Jennings CO.-PARISH Decatur
 STATE Kansas DATE COMMENCED 4-7-61 DATE COMPLETED 6-27-61
 PURPOSE OF WORK-OVER Wash down abandoned hole and convert to WI.

TEST AND COMPLETION DATA

	BEFORE WORK-OVER	ZONES TESTED		AFTER WORK-OVER	
	Formation	ASP-D			Howard
Date of Test				6-27-61	
Depth of Prod. Interval				3245-50	3518-23 3555-60 3584-89
Production Oil - BPD				15-Fr	all Zones
Gas - MCF					
Water - BPD				27	
GOR					
BHP - PSI					
Corrected API Gravity				37.5	
Producing Conditions				Pump	
Artificial Stimulation				500 Acid	1500 Acid

WORK-OVER COST _____ PAYOUT PERIOD _____

SUMMARY OF OPERATION:

Moved in Rotary Tools. Drilled cement plugs & washed down to 3732.
 Ran 117 jts. 4-1/2" OD 9.5# J-55 R-2 SS casing (new) set at 3671.

Cemented with 800 sacks. Ran G-M Log from 3150 to 3629.

Perf. Lans. "G" 3584-89 (3 jets/ft.) - 500 gal. 15% Acid.

Perf. Lans. "F" 3555-60 (3 jets/ft.) - 500 gal. 15% Acid.

Perf. Lans. "D" 3518-23 (3 jets/ft.) - 500 gal. 15% Acid.

Perf. Howard 3245-50 (3 jets/ft.) - 500 gal. 15% Acid.

Tested Lans. "D"- "F"- "G" 4 hrs. Recovered 15 BO & 10 BW.

Tested Howard 4 hrs. Recovered 8 BF w/tr. of oil.

FBTD 3629

Moved in Pulling Unit.

Tested Lans. "G" 8 hrs. Recovered 30.85 BO & 20.60 BW.

Tested Lans. "F" 8 hrs. Recovered 33.75 BO & 17.81 BW.

Tested Lans. "D" 9 hrs. Recovered 31.60 BO & 16.90 BW.

Swabbed at a rate of 90 BO & 60 BW from Lans (T-3442) Zone "D" perfs 3518-23,
 Zone "F" perfs 3555-60, Zone "G" perfs 3584-89 & Howard (T-3240) perfs
 3245-50 after 2000 gal acid.

APPROVED *W. H. H. H.*

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

October 20, 1969

15-039-00480-00-01

WELL PLUGGING AUTHORITY

Well No.	1W
Lease	R. L. Skubal "B"
Description	NE NE NE 35-4-27W
County	Decatur
Total Depth	3880
Plugging Contractor	Co. Tools


Texaco, Inc.
614 Bitting Bldg.,
Wichita, Kansas 67202

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Very truly yours,


J. Lewis Brock, Administrator

Mr. W. L. Nichols Box 157 Morland, Kansas
is hereby assigned to supervise the plugging of the above
named well.