

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
P. O. BOX 17027  
WICHITA, KANSAS 67217

Rev. 6-3-74  
FORM CP-1

WELL PLUGGING APPLICATION FORM  
File One Copy

RECEIVED  
STATE CORPORATION COMMISSION

MAY 14 1975  
CONSERVATION DIVISION  
Wichita, Kansas

API Number 15 - 153 - 00028 - 00 - 02 (of this well)  
Lease Owner Pack Oil Company, Inc.  
Address P. O. Box 1198, Wichita, Kansas 67201  
Lease (Farm Name) Ruda #1 Well No. \_\_\_\_\_  
Well Location NW NW NW Sec. 23 Twp. 4 Rge. 33W (E) \_\_\_\_\_ (W) \_\_\_\_\_  
County Rawlins Total Depth 4493' Field Name \_\_\_\_\_  
Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well  SWD Well \_\_\_\_\_ Rotary D & A \_\_\_\_\_  
Well Log attached with this application as required yes  
Date and hour plugging is desired to begin immediately

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

David Litan

Address Wichita, Kansas

Plugging Contractor Knight Casing Pulling Co., Inc. License No. 624

Address Box 405, Chase, Kansas 67524

Invoice covering assessment for plugging this well should be sent to:

Name Pack Oil Company, Inc.

Address P. O. Box 1198, Wichita, Kansas 67201

and payment will be guaranteed by applicant or acting agent.

Signed: *Neil Knight*

Applicant or Acting Agent

Date: \_\_\_\_\_

May 13, 1975

COPY

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- AMERADA PETROLEUM CORP.  
Farm- Ruda No. 1


SEC. 23 T. 4 R. 33W  
NW NW NW

Total Depth. 4493'  
Comm. 1-20-59  
Shot or Treated.  
Contractor.  
Issued. 6-13-59

Comp. 1-30-59

County Rawlins

KANSAS



RECEIVED  
CONSERVATION DIVISION  
Wichita, Kansas

CASING:

8 5/8" 263' cem w/225 sk.

Elevation. 2996'

4350' - 4 1/2" cem w/250 sk Top cement 2706'

Production. Dry See rework below

Figures Indicate Bottom of Formations

sandy shale	187
shale	820
sandy shale & sand	1150
shale & shells	2280
Anhydrite	2330
shale & shells	2380
red bed, shale & shells	2705
shale & lime	3792
lime	3920
lime & shale	3954
lime	4239
lime & shale	4313
lime	4470
lime (Mississippi)	4493
Total Depth	

TOPS: SCOUR	
Heebner	3870
Toronto	3897
Lansing	3911
Base Kansas City	4145
Cherokee	4370
Mississippi	4464

AMERADA PETROLEUM #1 RUDA 23-4-33W NW NW NW

Contr. RAWLINS County

E 2996 Comm. Comp. 1-30-59 IP D & A

Tops	Depth	Datum	Casing
			8" 450
HEEB	3870	-874	DST 3900-20/2 HR, 185' MDY
TOR	3897	-901	365' CL SW, BHP 1225#
LANS	3911	-915	DST 3922-54/2 HR, 185' M, F
			SPKS 0, BHP 810#
B/KC	4145	-1149	DST 3962-4004/2 HR, 150' G,
			OCM, 240' H MGO, BHP 940#
CHERO	4370	-1374	DST 4052-82/1 HR, 40' M, BHP
			DST 4292-4313/75", 90' M, BHP
MISS	4464	-1468	
			WATERMAN POOL. DST 4315-4400
TD	4493	-1497	HR, 30' M, BHP

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

MILES JACKSON #1 RUDA 23-4-33W NW NW NW

Contr. BADGER DRLG RAWLINS County

E 2996 Comm. Comp. 4-10-59 IP 87 BOPD

Tops	Depth	Datum	Casing
			8" 450
TOP	3706	-710	4" 4350
HEEB	3872	-876	DST 3900-20/2 HR, 185' MDY SW, 365' CL SW,
TOR	3901	-905	BHP 1225#
LANS	3913	-917	DST 3922-54/2 HR, 185' M, F SPKS 0, BHP 810#
			DST 3962-4004/2 HR, 150' G, 90' OCM, 240' H MGO, BHP 940#
B/KC	4146	-1150	DST 4052-82/1 HR, 40' M, BHP 50#
CHERO	4370	-1374	DST 4292-4313/75", 90' M, BHP 390#
MISS	4466	-1470	DST 4315-4400/1 HR, 30' M, BHP 40#
			NEW INFO: CO: PERF 24/4081-87: ACID 500:
			FU 50' O: ACID 2000: SWB 1 BOPH: 16/4002-
			06: 16/3986-90: SWB 1 BFPH: ACID 8000:
			WATERMAN POOL PKR 3950: PMP 38 80/16
TD	4493	-1497	HR & WTR: PMP 50 80/3 DAYS FROM LANS

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

State of Kansas



15-153-00028-0002

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

May 14, 1975

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Ruda
Description	NW NW NW 23-4-33W
County	Rawlins
Total Depth	4493'
Plugging Contractor	Knight Casing Pulling


Pack Oil Company, Inc.  
P. O. Box 1136  
Wichita, Kansas 67201

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,

  
J. Lewis Brock, Administrator

Mr. Gilbert Balthazor, Route 1, Falco, Kansas  
is hereby assigned to supervise the plugging of the above  
named well.