

RECEIVED
JUL 15 2004
KCC WICHITA

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-155-20125-0D-02 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date. 2/05

WELL OPERATOR Whitetail Crude, Inc/Fritzler Trucking, Inc KCC LICENSE # 31627
(owner/company name) (operator's)

ADDRESS P O Box 544 CITY Ness City

STATE KS ZIP CODE 67560-0544 CONTACT PHONE # (785) 798-3641

LEASE Dion OWWO WELL# 1 SEC. 3 T. 23S R. 10W (East/West)

NE NW SW SPOT LOCATION/0000 COUNTY Reno

2310 FEET (in exact footage) FROM S/~~N~~ (circle one) LINE OF SECTION (NOT Lease Line)

990 FEET (in exact footage) FROM E/~~W~~ (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 253 CEMENTED WITH _____ SACKS

PRODUCTION CASING SIZE 4 1/2 SET AT 3770 CEMENTED WITH 200 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 3222-32, 3351-56, CIBP @ 3320

ELEVATION 1759 T.D. 3774 PBTD 3320 ANHYDRITE DEPTH _____
(~~G.K.K.~~/K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Sand off 4 1/2 casing to 50' above perfs (3290), spot 4 sks cement thur dump bailer, shoot off 4 1/2 casing @ 2500', pull casing to 1400', pump 35 sk plug @ 1400', pull to 900', pump 35 sk plug, pull to 250'; circulate cement to surface, lay down rest of 4 1/2 & top off 8 5/8 to surface - - - 60-40 poz 6% gel cement
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? no IS ACO-1 FILED? yes

If not explain why? no logs received from Blue Ridge Petroleum Corp

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Mike J. Fritzler, President PHONE# () 785-798-3641

ADDRESS P O Box 544 City/State Ness City, KS 67560-0544

PLUGGING CONTRACTOR Fritzler Trucking, Inc KCC LICENSE # 3831
(company name) (contractor's)

ADDRESS P O Box 544, Ness City, KS 67560-0544 PHONE # () 785-798-3641

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) ASAP 7-19-04 Plugged

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 7/14/04 AUTHORIZED OPERATOR/AGENT: Mike J. Fritzler
(signature)

Mike J. Fritzler, President