

RECEIVED
APR 05 2004
KCC WICHITA

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 129-30077-0001 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date _____.

Well Operator: High Plains Production, LLC KCC License #: 32390 11/04
(Owner / Company Name) (Operator's)

Address: PO Box 228 City: Savoy

State: Texas Zip Code: 75479 Contact Phone: (903) 965 - 5403

Lease: White Well #: 1-18 Sec. 18 Twp. 33 S. R. 41 East West

NW - SE Spot Location / QQQQ County: Morton

2080 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1980 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8.625" Set at: 1485' Cemented with: unknown Sacks

Production Casing Size: 5.500" Set at: 3438' Cemented with: 250 Sacks

List (ALL) Perforations and Bridgeplug Sets: 2891'-2896', 2900'-2904', 2910'-2913', 2924'-2928', 2932'-2938', 2964'-2970', 3175'-3179', 3199'-3203'; CIBP @ 3224'; 3233'-3239'

Elevation: 3451' (G.L. / K.B.) T.D.: 5080' PBTD: 3224' Anhydrite Depth: unknown
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): set a CIBP at 2800', 2 sx cement on top of plug, perforate at 1500', and circulate 60/40 Pozmix cement back to the surface to fill the 5.500" casing and the annulus between the surface casing and production casing. cut off the casing 3' below ground level and weld a plate on top.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? Log is not available.

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Ron Osterbuhr

Phone: (620) 275 - 7888

Address: P.O. Box 1152 City / State: Garden City, KS 67846

Plugging Contractor: to be determined Allied Cement Company KCC License #: 99996
(Company Name) (Contractor's)

Address: 602 N. Clay Medicine Lodge, KS 67104 Phone: () -

Proposed Date and Hour of Plugging (if known?): unknown 4-15-04, Plugged

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent
Date: 3/31/2004 Authorized Operator / Agent: Ron Osterbuhr (Signature)