

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
Wichita, Kansas 67217

Rev. 3-15-72
FORM CP-1
RECEIVED
STATE CORPORATION COMMISSION

SEP 30 1974

WELL PLUGGING APPLICATION FORM
File One Copy

CONSERVATION DIVISION
Wichita, Kansas

9-30-74

15-153-20185-06-00

Lease Owner ABERCROMBIE DRILLING, INC.
Address 801 UNION CENTER, WICHITA, KANSAS 67202
Lease (Farm Name) MYERS Well No. #1
Well Location 150' SE of C NW NE Sec. 35 Twp. 4S Rge. (E) 34 (W)
County RAWLINS Total Depth 4660' Field Name _____
Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ Rotary D & A X
Well Log filed with application as required Yes
Date and hour plugging is desired to begin 8:00 p.m. September 25, 1974

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

DON FAVINGER Address HILL CITY, KANSAS

Plugging Contractor Abercrombie Drilling, Inc. License No. _____

Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to:

Name Abercrombie Drilling, Inc.

Address 801 Union Center, Wichita Kansas 67202

and payment will be guaranteed by applicant or acting agent.

Signed: Jerry A. Langrehr
Applicant or Acting Agent
Jerry A. Langrehr, Exec. V.P.
Date: September 26, 1974

Operator Abercrombie Drilling, Inc.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. #1	Lease Name MYERS	Dry Hole
S 35 T 4S R 34 E W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sand & Shale	0	288	<u>ELECTRIC LOG</u>	
Shale & Shells	288	690	Anhydrite	2804
Shale & Sand	690	2379	B/Anhydrite	2841
Anhydrite	2379	2411	Heebner	3991
Shale	2411	3028	Toronto	4023
Shale & Lime	3028	3200	Lansing	4036
Lime & Shale	3200	3700	B/Kansas City	4280
Lime	3700	4010	Marmaton	4315
Lime & Shale	4010	4070	Cherokee	4453
Lime	4070	4660	Mississippian	4638
Rotary Total Depth		4660	ELTD	4662
<p>DST #1 (4112-4140) 30", 60", 60" Recovered 240' watery mud, 210' slightly muddy water. IFP 0#-106#; IBHP 1322#; FFP 962#-787#.</p> <p>DST #2 (4422-4440) 30", 30", 30", 30" Recovered 15' Mud. IFP 35#; IBHP 35#; FFP 35#; FBHP 35#.</p> <p>DST #3 (4439-4460) 30", 30", 30", 30" Recovered 260' Drilling Mud. IFP 130#-153#; IBYP 1102#; FFP 165#-165#; FBHP 939#.</p> <p>1st Plug set @ 1900' with 70 Sacks 2nd Plug set @ 280' with 20 Sacks 3rd Plug set @ 40' with 10 Sacks</p>				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<p align="center"><i>Jack K. Wharton</i> Jack K. Wharton Signature Geologist _____ Title September 26, 1974 _____ Date</p>

State of Kansas



15-153-20185-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

October 1, 1974

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Myers
Description	150' SE/C NW NE 35-4-34W
County	Rawlins
Total Depth	4660'
Plugging Contractor	Abercrombie Drlg., Inc.


Abercrombie Drilling, Inc.
801 Union Center
Wichita, Kansas 67202

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,


J. Lewis Brock, Administrator

Mr. W. L. Nichols, P. O. Box 157, Morland, Kansas 67650
is hereby assigned to supervise the plugging of the above
named well.