

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
**Type or Print on this Form
Form must be Signed
All blanks must be Filled**

Lease Operator: Castelli Exploration, Inc.
 Address: 6908 N.W. 112th St. Oklahoma City, OK 73162
 Phone: (405) 722-5511 Operator License #: 31021
 Type of Well: Gas Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 9/13/04 (Date)
 by: Steve Middleton (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
Mississippi Depth to Top: 5032' Bottom: 5078' T.D. 5092'
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. 5

API Number: 15 - 033-21392-00-00
 Lease Name: Gregg
 Well Number: 1-19
 Spot Location (QQQQ): C - E/2 - W/2 - SE
1320 Feet from North / South Section Line
1650 Feet from East / West Section Line
 Sec. 19 Twp. 33 S. R. 16 East West
 County: Comanche
 Date Well Completed: 03/18/04
 Plugging Commenced: 09/14/04
 Plugging Completed: 09/16/04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	45'	20"	45'	0
		Surface	315'	13 3/8"	315'	0
		Surface	5137'	4 1/2"	5137'	3450'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Displaced hole w/9.5# plug mud. Set CIBP @ 4980' w/2 sks cmt on top. Cut off 4 1/2" csg @ 3490', placed plus as follows: 50 sks cmt 860'-660', 90 sks cmt 345'-235', 30 sks cmt 40'-0' with mud spacing each plug.

Name of Plugging Contractor: Sargent & Lillard Casing Pulling, Inc. License #: 32833
 Address: P.O. Box 1450, Woodward, OK 73802-1450
 Name of Party Responsible for Plugging Fees: Castelli Exploration, Inc.
 State of Oklahoma County, Oklahoma, ss.

**RECEIVED
OCT 29 2004
KCC WICHITA**

 (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Christophe J. Greenlee Expl Geol.
 (Address) 6908 N.W. 112th St., Oklahoma City, OK 73162

SUBSCRIBED and SWORN TO before me this 26th day of October, 2004



TISHA L. BRAUN
 Canadian County
 Notary Public in and for
 State of Oklahoma

Tisha L. Braun
 Notary Public

My Commission Expires: 6/23/08

Bm

RECEIVED
OCT 29 2004
KCC WICHITA

SARGENT AND LILLARD CASING PULLING, INC.

P.O. BOX 1450
WOODWARD, OKLAHOMA 73802

Nº 0860

DAILY REPORT

DATE 9-14-04 FROM _____ TO _____
COMPANY _____ FARM NO. _____

Castelli Exp. Gregg 1-19

HOURS WORKED	NAME
<u>11</u>	<u>Marlin Clark</u>
<u>11</u>	<u>Patrick Underhill</u>
<u>11</u>	<u>Rusty Walkup</u>

CONTRACTOR'S TIME 1 hrs. COMPANY'S TIME 10 hrs.

REMARKS: MIRU pole + pump truck disp hole w/120
bbl. 9.5# plug mud RU case wireline set CIBP
e 9980' w/ 2 SKS cnt on top RU Jacks pull slips
take FP. shut down.

10 hrs @ 90⁰⁰ = 900⁰⁰
CIBP = 1250⁰⁰
2150⁰⁰

RECEIVED
OCT 29 2004
KCC WICHITA

SARGENT AND LILLARD CASING PULLING, INC.

P.O. BOX 1450
WOODWARD, OKLAHOMA 73802

Nº 0861

DAILY REPORT

DATE 9-15-04 FROM _____ TO _____

COMPANY

FARM NO.

Castelli Exp. Gregg 1-19

HOURS WORKED

NAME

10

Maclin Clark

10

Patrick Underhill

10

Rusty Walkup

CONTRACTOR'S TIME 5 hrs. COMPANY'S TIME 5 hrs.

REMARKS: Work pipe shoot 4 1/2 e 4250, 3540 + 3450

Lay down 60 JTS shut down

5 hrs. @ 90⁰⁰ - 450⁰⁰

3 shots @ 250⁰⁰ - 750⁰⁰

2580' 4 1/2" .60 - 1548⁰⁰

2748.00

RECEIVED
OCT 29 2004
KCC WICHITA

SARGENT AND LILLARD CASING PULLING, INC.

P.O. BOX 1450
WOODWARD, OKLAHOMA 73802

N^o 0862

DAILY REPORT

DATE 9-16-04 FROM _____ TO _____

COMPANY

FARM NO.

Castelli Exp Gregg 1-19

HOURS WORKED	NAME
<u>11</u>	<u>Marlin Clark</u>
<u>11</u>	<u>Patrick Underhill</u>
<u>11</u>	<u>Rusty Walkup</u>

CONTRACTOR'S TIME 6 hrs COMPANY'S TIME 5 hrs

REMARKS: pump 50 sks cmt from 860'-660'
Lay down 12 JTS up to 345' pump 90 sks
cmt from 345'-235' Lay 4 1/2 down RD Jacks
pump 30 sks cmt from 40'-0' RD MO.
pump #1 - 550.00
pump #2 - 150.00
Cost Del - 1324.47
889.37 @ 90 - 533.62
5 hrs @ 90 - 450.00
3008.09