



Rawlins County. Sec. 20 Twp. 4S Rge. 36 (W)
Location as "NE/CNW&SW" or footage from lines C NW SW
Lease Owner The Frontier Refining Company
Lease Name Briney "A" Well No. 1
Office Address 4040 E. Louisiana Ave., Denver 22, Colorado
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed Nov. 25 19 62
Application for plugging filed Nov. 26 19 62
Application for plugging approved Nov. 23, 9:30 P.M. (verbal, telephone) 62
Plugging commenced Nov. 25 19 62
Plugging completed 4:30 P.M. Nov. 25 19 62
Reason for abandonment of well or producing formation Non-productive

If a producing well is abandoned, date of last production - 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty, Hays, Kansas
Producing formation none Depth to top - Bottom - Total Depth of Well 4985 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippian	water	4884	4985	8 5/8" 24#	348' set @ 354' KB	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled w/10.5#/gal mud, 53 vis.
20 sx cement, 1/3 sx hulls plug set from 650' to 585' KB
(in 7 7/8" hole) Displace thru 4 1/2" drill pipe
20 sx cement, 1/3 sx hulls plug set from 300' to 238' KB
(in 8 5/8" surface csg) Displace thru drill pipe
10 sx cement, 1/2 sx hulls, plug set from 40' to 2'
(in 8 5/8" surface csg) Displace thru Kelley
Solid bridge set @ 40' which would hold weight of Kelley

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Murfin Drilling Company
Address 617 Union Center, Wichita 2, Kansas

STATE OF Colorado, COUNTY OF Denver, ss.
John L. Corkill (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John L. Corkill
John L. Corkill, Petroleum Engineer
4040 E. Louisiana Ave., Denver 22, Colorado
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of November 19 62

My commission expires April 19, 1965

Notary Public.