

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-153-20,585-00-01

LEASE NAME Wahrman

WELL NUMBER 6-41

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

4620 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 6 TWP. 4 RGE. 36 (E) or (W)

COUNTY Rawlins

Date Well Completed 4/85

Plugging Commenced 12/19/85

Plugging Completed 12/19/85

LEASE OPERATOR White & Ellis Drilling, Inc.

ADDRESS 401 E. Douglas-Suite 500 Wichita, Kansas 67202

PHONE # (316) 321-5050 OPERATORS LICENSE NO. 8301
5420

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4985'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface		-0-	343'	8 5/8"	343'	-0-
Production		343'	4985'	4 1/2"	4984'	2054'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Bottom Perfs w/sand to 4671', Put in W/water, 4 sks cmt. on top, w/dump baler.
Top w/3 sks hulls, 3 sks gel, 100 sks cmt, 1 sk hull, 42 sks gel, 8 5/8" wiper plug,
and 80 sks cmt. (cmt 60/40 poz 6% gel, 3% cc) Pumped in w/ pump truck.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Hembree Well Service, Inc. License No. 6907

Address 302 E. Sycamore, Box 458, Ness City, 67560

STATE OF KANSAS COUNTY OF SEDGWICK

STATE CORPORATION COMMISSION
 1-21-86
 JAN 21 1986
 CONSERVATION DIVISION

Ernest Sifford (Employee of Operator) or (Owner) of above-described well, being first duly sworn on oath, says: That I have known the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
 401 E. Douglas - Suite 500
 (Address) Wichita, Ks. 67202

SUBSCRIBED AND SWORN TO before me this 16th day of January, 19 86

[Signature]
 Notary Public
 Carolyn J. Tjaden

My Commission Expires:

