

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-20607-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 23-34S-21W
2310 feet from S Section Line, 330 feet from W Section Line
Lease Name: BARBY Well #: 2-23
County: CLARK Total Vertical Depth: 5600 feet

Operator License No.: 5055
Op Name: C. H. TODD, INC.
Address: 1000 N. TYLER
WICHITA, KS 67212

COND Size: 20 feet: 95 WITH 350 SX CMT
II Size: 8.625 feet: 874 WITH 700 SX CMT
PROD Size: 5.5 feet: 5512 WITH 300 SX CMT
SURF Size: 13.38 feet: 320 WITH 530 SX CMT

\$182⁰⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/21/2004 9:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 40 SX CMT & 500# HULLS. PLUG AT 900' WITH 50 SX CMT. PLUG AT 400' WITH 30 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: PARTIAL
Date/Time Plugging Completed: 10/21/2004 1:30 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 5471'. PUMP 40 SX CMT & 500# HULLS. LOAD HOLE WITH MUD. 1ST PLUG SPOT 50 SX CMT AT 900'. 2ND PLUG PULL TO 400' & SPOT 30 SX CMT. 3RD PLUG PULL TO 40' & SPOT 15 SX CMT. STAYED FULL.

Perfs:


Top	Bot	Thru	Comments
5420	5430		
4300	4308		

RECEIVED
OCT 27 2004
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2771' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed _____

(TECHNICIAN)

INVOICED
DATE 10-27-04
WV. NO. 2005060713

Form CP-43