

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-033-21182-00-00  
Spot: E2E2E2SE Sec/Twnshp/Rge: 7-31S-19W  
1320 feet from S Section Line, 0 feet from E Section Line  
Lease Name: LOHRDING Well #: 3  
County: COMANCHE Total Vertical Depth: 5415 feet

Operator License No.: 32384  
Op Name: COMANCHE RESOURCES COMPANY  
Address: 6520 N. WESTERN AVE., SUITE 300  
OKLAHOMA CITY, OK 73116

CIBP Size: feet: 5000 WITH 2 SX CMT  
COND Size: 20 feet: 86 WITH 200 SX CMT  
PROD Size: 4.5 feet: 5412 WITH 170 SX CMT  
SURF Size: 8.625 feet: 656 WITH 350 SX CMT

99  
\$175

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/14/2004 12:45 PM  
Plug Co. License No.: 33115 Plug Co. Name: NORTH STAR WELL SERVICES, INC.  
Proposal Revd. from: DENNIS DYE Company: COMANCHE RESOURCES Phone: (405) 368-5927

Proposed Plugging Method: CIBP @ 5000' WITH 2 SX CMT. PLUG AT 1100' WITH 15 SX GEL & 50 SX CMT. PLUG AT 680' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/14/2004 2:30 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

CIBP @ 5000' WITH 2 SX CMT ON TOP. 1ST PLUG PULL TO 1100' & SPOT 15 SX GEL & 50 SX CMT. 2ND PLUG PULL TO 680' & SPOT 50 SX CMT. 3RD PLUG PULL TO 40' & PUMP 15 SX CMT. STAYED FULL.

Perfs:


Top	Bot	Thru	Comments
5136	5148		
5097	5102		

RECEIVED  
OCT 25 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 4360' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed \_\_\_\_\_ (TECHNICIAN)

INVOICED  
DATE 10-25-04  
SERIAL 2005060692