

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-01601-00-00  
Spot: NWNWNW Sec/Twnshp/Rge: 6-23S-11W  
330 feet from N Section Line, 330 feet from W Section Line  
Lease Name: BROCK B J Well #: 1  
County: STAFFORD Total Vertical Depth: 3570 feet

Operator License No.: 32432  
Op Name: LA VETA OIL & GAS, LLC  
Address: PO BOX 780  
MIDDLEBURG, VA 20118

PROD Size: 8.625 feet: 3531 UNKNOWN  
SURF Size: 13.75 feet: 248 UNKNOWN

\$ 110<sup>63</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/20/2004 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SPOT 50 SX CMT & 250# HULLS AT 2387'. PLUG AT 620' WITH 15 SX GEL - 200# HULLS - 80 SX CMT. PLUG AT 270' WITH 80 SX CMT. PLUG AT 40' WITH 25 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/20/2004 12:40 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

CASING COLLAPSED IN HOLE. COMPANY HAS MADE NUMEROUS ATTEMPTS TO RETURN WELL TO PRODUCTION. GOT TUBING TO 2406'. COULD NOT GET ANY FURTHER. SPOTTED 50 SX CMT & 250# HULLS AT 2387'. SPOTTED PLUGS THROUGH TUBING. 1ST PLUG AT 620' WITH 15 SX GEL - 200# HULLS - 80 SX CMT. 2ND PLUG AT 270' WITH 80 SX CMT. 3RD PLUG AT 40' WITH 25 SX CMT.

Perfs:


| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 3531 | 3570 |      |          |

RECEIVED  
OCT 27 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND ACID. RECOVERED 1500' OF 8 5/8" CASING.

Plugged through: TBG

District: 01



Signed

Richard W. Lacey  
(TECHNICIAN)

INVOICED  
DATE 10-27-04  
INV. NO. 2005060705

Form CP-23