

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-00047-00-00
Spot: SESE Sec/Twnshp/Rge: 30-34S-21W
660 feet from S Section Line, 660 feet from E Section Line
Lease Name: CAMPBELL UNIT M C Well #: 1
County: CLARK Total Vertical Depth: 5749 feet

Operator License No.: 33185
Op Name: QUAIL OIL & GAS, LC
Address: 109 HAMPTON CT.
GARDEN CITY, KS 67846

CIBP Size: feet: 5300 WITH 2 SX CMT
CIBP Size: feet: 5596
COND Size: 19 feet: 249 WITH 150 SX CMT
PROD Size: 5.5 feet: 5749 WITH 250 SX CMT
SURF Size: 10 feet: 588 WITH 150 SX CMT

84
\$ 186

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/21/2004 10:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Revd. from: JOHN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: SET CIBP, SAND OFF, PUMP HULLS & CMT FOR BOTTOM. PLUG AT 1000' WITH 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/21/2004 12:00 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

CIBP @ 5300' WITH 2 SX CMT ON TOP. 1ST PLUG AT 1010' WITH 15 SX GEL & 30 SX CMT. 2ND PLUG PULL TO 600' & PUMP 70 SX CMT. 3RD PLUG PULL TO 30' WITH 15 SX CMT. STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
5685	5694		
5526	5540		

RECEIVED
OCT 27 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2500' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
OCT 22 2004
KCC Dodge City

Signed



(TECHNICIAN)

INVOICED

DATE

10-27-04

INV. NO.

2005060710

Form CP 2/3