

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-083-20747-00-01  
Spot: SWSESE Sec/Twnshp/Rge: 4-23S-22W  
660 feet from S Section Line, 735 feet from E Section Line  
Lease Name: QUERBACH Well #: OWWO 3  
County: HODGEMAN Total Vertical Depth: 5087 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

CIBP Size: feet: 3495 WITH 2 SX CMT  
PROD Size: 5.5 feet: 4948 WITH 350 SX CMT  
SURF Size: 8.625 feet: 1338 WITH 500 SX CMT

\$165.<sup>33</sup>

Well Type: SWD UIC Docket No: D24874.0 Date/Time to Plug: 10/25/2004 1:00 PM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: SCOTT CORSAIR Company: AMERICAN WARRIOR Phone: (785) 398-2270

Proposed Plugging Method: CIBP @ 3495' & 2 SX CMT. PLUG AT 1360' WITH 50 SX CMT. PLUG AT 550' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/25/2004 3:00 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PARTED TUBING & JUNK IN HOLE 3550' TO BOTTOM. SET CIBP @ 3495' WITH 2 SX CMT ON TOP. 1ST PLUG PULL TO 1360' & SPOT 15 SX GEL & 50 SX CMT. 2ND PLUG PULL TO 550' & SPOT 40 SX CMT. 3RD PLUG PULL TO 40' & SPOT 15 SX CMT. STAYED FULL.

Perfs:


Top	Bot	Thru	Comments
4948	5087	OH	

RECEIVED  
OCT 28 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2000' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

(TECHNICIAN)

INVOICED  
DATE 10-28-04  
AMOUNT 2005060717

Form CR-2/B