

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-075-20640-00-00  
Spot: SE Sec/Twnshp/Rge: 27-21S-40W  
1320 feet from S Section Line, 1320 feet from E Section Line  
Lease Name: STANCO Well #: 1-27  
County: HAMILTON Total Vertical Depth: 2900 feet

Operator License No.: 32920  
Op Name: W. R. WILLIAMS, INC.  
Address: PO BOX 15163  
AMARILLO, TX 79105

PROD Size: 4.5 feet: 2897 WITH 520 SX CMT  
SURF Size: 8.625 feet: 256 WITH 165 SX CMT

*\$94<sup>25</sup>*

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/19/2004 10:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: DAVE OLSON Company: W.R. WILLIAMS Phone: (806) 374-4555

Proposed Plugging Method: SQUEEZED WITH 250 SX CMT WITH CMT RETAINER @ 2816'. PUMP 3 SX HULLS AND 15 SX CMT. DISPLACE WITH FRESH WATER, PERF 4 HOLES @ 700', PUMP 155 SX CMT AND CIRCULATE TO SURFAC.E

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/19/2004 11:30 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CMT RETAINER @ 2816'. ANHYDRITE BASE @ 2359'. PUMP 200# HULLS & 15 SX CMT ON BOTTOM. PUMP WATER SPACER BACK TO 1200'. PUMP 10 SX CMT. FILL CASING TO SURFACE WITH WATER. PRESSURE TO 1000 PSI. RELEASE PRESSURE. PERFORATE 4 HOLES @ 700' IN 4 1/2" CASING. BREAK CIRCULATION WITH WATER. STRONG BLOW ON 4 1/2" X 8 5/8" ANNULUS THEN PUMP 175 SX CMT. CMT TO SURFACE. CIRCULATE 10 SX CMT TO PIT. MAXIMUM PRESSURE 500#.

Perfs:

Top	Bot	Thru	Comments
2860	2866		
2833	2836		
2822	2830		
2784	2794		
2742	2847		

RECEIVED  
OCT 28 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

RECEIVED  
OCT 26 2004  
KCC Dodge City

Signed Ken Jehlik  
(TECHNICIAN)

INVOICED  
DATE 10-28-04  
INV. NO. 2005060721

Form CP-278