

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-153-20,573-00-00  
SE SE, Sec. 5, T 4 S, R 35 W/EX  
660 feet from SE N/S section line  
660 feet from SE W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9673

Lease Name Fikan Well # 1

Operator: Perry G. Larson  
Name & R.R. #2 Box 1  
Address McDonald, Ks. 67745

County Rawlins

Well Total Depth 4875 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8<sup>5/8</sup> feet 340

158.44

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D&A XX

Other well as hereinafter indicated     

Plugging Contractor Abercrombie Drilling License Number 5422

Address Wichita,

Company to plug at: Hour: AM Day: 25 Month: September Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Wally Towns

(company name) Abercrombie (phone)     

were: Order 195 sks 50/50 pozmix 6% gel 3% cal. cl., 1 sk flo-cel and 8<sup>5/8</sup> plug and  
1 sk hulls. Spot with drill pipe with no less than 36 vis. mud between all plugs,  
with good circulation and no fluid loss.

Signed       
(TECHNICIAN)

Plugging Operations attended by Agent?: All      Part      None XX

Operations Completed: Hour: 7 AM Day: 25 Month: September Year: 19 84

ACTUAL PLUGGING REPORT     

1st plug @ 3000 w/25 sks

2nd plug @ 2280 w/100 sks 1 sk flo-cel

3rd plug @ 380 w/40 sks

4th plug @ 40 w/8<sup>5/8</sup> plug 1 sk hulls and 10 sks cmt

10 sks in Rat Hole and 10 sks in Mouse Hole

RECEIVED  
STATE CORPORATION COMMISS  
10-1-84  
OCT 01 1984

Remarks: Cemented by Sun

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated  
and that I ~~did~~ / did not) observe this plugging.

Signed Gilbert P. Lenker  
(TECHNICIAN)

INVOICED

DATE 10-8-84

INV. NO. 4113

FORM CP-2/3  
Rev. 9-82

9-28-84  
27