

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-00434-00-00
Spot: NENENE Sec/Twnshp/Rge: 27-13S-15W
4950 feet from S Section Line, 330 feet from E Section Line
Lease Name: DUMLER D Well #: 1-2
County: RUSSELL Total Vertical Depth: 3079 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

COND Size: 10 feet: 948
PROD Size: 5.5 feet: 3320
SURF Size: 8.625 feet: 2575

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/21/2004 9:00 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: ED POE Company: POE SERVICING INC Phone: (785) 475-3422

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
Casing leaks.
Poe Well Service ran into cement slurry with bit at 500' in hole with drill bit.
Took pump in rate of 1 1/2 BBL fluid per minute.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/21/2004 10:30 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Allied Cementing rigged to 5 1/2" casing - pumped 100 sxs 60/40 pozmix to get fluid to start circulating out of 10" casing - used 600# P.I.P.
Pumped an additional 80 sxs to circulate cement out of 10" casing with 200# S.I.P. on the 5 1/2" casing.
Did not use Log Tech to perforate at 300' since cement circulated.
Ran one joint tubing to the bottom of 15" casing - pumped 30 sxs to circulate cement to surface.

Perfs:

RECEIVED
OCT 25 2004
KCC WICHITA

Remarks: LEASE ORIGINALLY KNOWN AS BILLINGS C-1. ALLIED CEMENTING COMPANY-TICKET#18827.

Plugged through: CSG

District: 04

Signed


(TECHNICIAN)

OCT 21 2004

STEARNS DRILLING CO

#1

BILLINGS C

33

27-13-15W

NE NE NE

Contr.

RUSSELL

County

E. 1895

Comm.

7-13-47

Comp.

1-30-48

IP

39 EOPD

PHY FCT

Tops	Depth	Datum
ALH	948	+947
LANS	3067	-1172
ARB	3318	-1423
T. D.	3331	-1436

Casing

15" 325 SWB 25 50/3 HRS:
 10" 948
 8" 2575
 5" 3320

SO 3328-31'

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS