

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-20875-00-00  
Spot: NENWNW Sec/Twnshp/Rge: 9-12S-15W  
4950 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: SUTTON Well #: 8  
County: RUSSELL Total Vertical Depth: 2975 feet

Operator License No.: 5259  
Op Name: MAI OIL OPERATIONS, INC.  
Address: 4514 COLE AVE., STE 740, LB 30  
DALLAS, TX 75205

PROD Size: 5.5 feet: 2974 w/250 sxs cmt  
SURF Size: 8.625 feet: 541 w/285 sxs cmt

#9669

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/04/2004 11:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: \_\_\_\_\_ Company: MAI OIL OPERATIONS, INC. Phone: (214) 219-8883

Proposed  
Plugging  
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/04/2004 12:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Tied onto casing and pumped 300 sxs 60/40 pozmix - 10% gel cement with 500# hulls.  
Max. P.S.I. 700#. S.I.P. 300#.  
Pressured backside to 500 P.S.I.

RECEIVED  
OCT 27 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY

Plugged through: CSG

District: 04

Signed Case Morris  
(TECHNICIAN)

INVOICED  
DATE 10-27-04  
CLERK 2005060707

OCT 22 2004

MAI OPERATIONS  
BOX 33, RUSSELL, KS.

#8 SUTTON

9-12-15W  
NE NW NW

CONTR DUKE DRLG. CO. CTY RUSSELL

GEOL FRANCIS WHISLER FIELD FAIRPORT

E 1706 KB CM 4/8/76 CARD ISSUED 6/23/76 IP P 50 BOPD + TR WTR  
TARKIO SD 2366-70

+	+	+
+	+	+
+	+	+

API 15-167-20,875

TOPS	DEPTH	DATUM
ANH	760	+ 946
GR HAY	2260	- 554
1ST TARK	2271	- 565
DOYER	2295	- 589
2ND TARK SD		
	2300	- 594
TARK LS	2334	- 628
3RD TARK SD		
	2362	- 656
ELM	2389	- 683
HOW	2546	- 840
TOP	2577	- 871
HEEB	2798	-1092
TOR	2820	-1114
LKC	2850	-1144
RTD	2975	-1269

8 5/8" 541/285sx, 5 1/2" 2974/250sx  
NO LOG  
NO DST'S  
MICT - PF 2858-61, 2879-81, 2892-95, AC  
3000, SWB LD, SWB 10.44 BFPH, BP @2462  
PF TARKIO SD 2366-70, FRAC 20,000 GW +  
12,500# SD, SWB 24 BFPH, POP

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

MAILED