

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23211-00-00
Spot: SWSESW Sec/Twnshp/Rge: 25-12S-20W
330 feet from S Section Line, 3630 feet from E Section Line
Lease Name: KOHL Well #: 1 SWD
County: ELLIS Total Vertical Depth: 1460 feet

Operator License No.: 8315
Op Name: KISKA OIL COMPANY
Address: 507 S. MAIN, #501
TULSA, OK 74103

PROD Size: 4.5 feet: 1460 w/450 sxs cmt
SURF Size: 8.625 feet: 285 w/170 sxs cmt

\$ 47⁴⁵

Well Type: SWD UIC Docket No: D21569.0 Date/Time to Plug: 10/01/2004 12:45 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: DON BRADSHAW Company: KISKA OIL COMPANY Phone: (918) 584-4251

Proposed
Plugging
Method:

Ordered 100 sxs cement and 500# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/01/2004 1:30 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Perfs:

Tied to 4 1/2" casing - obtained fluid rate - three plus barrels per minute.
Squeezed 55 sxs cement with 375# hulls.
Max. P.S.I. 200#. S.I.P. 200#.
Cement visible in annulus.
Total of 55 sxs Swift Multi-Density cement and 375# hulls.
Dakota 440' - 720'. Cedar Hills 926' - 1256'. Anhy. 1519' - 1563'.

RECEIVED
OCT 28 2004
KCC WICHITA

Remarks: SWIFT SERVICES, INC. STEWART TANK-WATER.

Plugged through: CSG

District: 04

Signed

Roger L. Moses

(TECHNICIAN)

INVOICED

DATE

10-28-04

INV. NO.

2005060718

Form CP-2/3

OCT 25 2004

D-21, 569

replacement card

BIG CREEK OIL OPER
HAYS KS 67601

25-12 -20W
336'FSL & 1190'FWL, SW/4


#1-SWD KOHL

site: 2 N & 3-1/4 E OF ELLIS KS
contr: EDSCO DRILLING

city: ELLIS
field: WEISNER

API 15-051-23211

fr date	app date	orig comp	crs issued	last revised
10/03/82	10/12/82	10/12/82	02/24/83	10/26/82



ELV: 2163 KB, 2156 GL SMP	
tops.....depth/datum	
FAIRPT.....240 +1823	
GRNHORN.....366 +1797	
GRANEROS.....404 +1759	
OAK SD.....440 +1723	
B/DAK SD.....720 +1443	
CED HILL.....926 +1237	
B/CED HILL.....1256 +907	
PSTD.....1422 +741	
RTD.....1480 +703	

IP status:
 SWDW, CED HILL 1198-1216,
 CORR & INFO REL: ORIG FR 330'FSL & 1450'FEL; WAS
 SWDW - TIGHT HOLE
 CSG: 8-5/8" 285 / 170 SX, 4-1/2" 1460 / 450 SX
 NO CORES OR DSTS
 MICT - CO, PF (CED HILL) 1198-1216, NO TRTMNT, SET
 2" TBG & PKR AT 1190, SWDW - INJECTION RATE
 SATISFACTORY 10/2/82

IMAGI