

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-20240-00-00
Spot: SENW Sec/Twnshp/Rge: 2-15S-28W
3300 feet from S Section Line, 3300 feet from E Section Line
Lease Name: J M COBERLY A Well #: 1
County: GOVE Total Vertical Depth: 4149 feet

Operator License No.: 31627
Op Name: WHITETAIL CRUDE, INC
Address: N HWY 283 PO BOX 544
NESS CITY, KS 67560

PROD Size: 4.5 feet: 4064 250 SX CMT
SURF Size: 8.625 feet: 291 170 SX CMT

\$134⁸⁴

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/05/2004 11:00 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: MIKE J FRITZLER Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: Ordered 260 sxs 60/40 pozmix and 500# hulls.
Junk in the hole up to 2600'. Emergency plug.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/05/2004 4:20 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Ran tubing to 2400' - spotted 35 sxs cement with 300# hulls.
POOH. Shot 4 1/2" casing off at 770' - pulled two joints and spotted 35 sxs cement.
Pulled 10 joints casing to 300' - circulated with 50 sxs cement.
POOH. Topped off with 30 sxs cement.
Total of 150 sxs Swift Multi-Density cement and 300# hulls.

Perfs:

Top	Bot	Thru	Comments
3960	3965		

RECEIVED
OCT 28 2004
KCC WICHITA

Remarks: SWIFT SERVICES, INC. FRITZLER TRUCKING-WATER.

Plugged through: TBG

District: 04

Signed Roger Moses
(TECHNICIAN)

INVOICED

DATE 10-28-04
INV. NO. 2025060720

OCT 26 2004

CHIEF DRLG. CO., INC. &
 BILL J. PORTER #1 J.M. COBERLY "A" 2-15-28W
 905 CENTURY PLAZA, WICHITA, KS. C SE NW
 CONTR CO. TOOLS CITY GOVE

GEOL _____ FIELD VALHALLA NO. DISC

E 2530 KB CM 2/5/75 CARD ISSUED 4/17/75 IP P 25 BOPD, 50% WTR
 KC 3960-65, GR 390

API 15-063-20,240

LOG	TOPS	DEPTH	DATUM
ANH		1967	+ 563
B ANH		2000	+ 530
HEEB		3668	-1138
TOR		3690	-1160
LANS		3707	-1177
BKC		4018	-1488
PAW		4123	-1593
LTO		4149	-1619

8-5/8" 291/170SX, 4 1/2" 4065/250SX
 DST (1) 3953-4050/30-30-60-30, REC 40'
 V50CM, 120'OCM, 20%O, 300'VHOCM
 (40%O), SIP 1165-1110#, FP 60-255#
 DST (2) 4019-4150/30-20-20-20, REC 10'
 M, SIP 68-68#, FP 68-68#
 DST (3) 3774-96 (W/SP)/PKR FAILED
 MICT - CO 4033', PF 20/3960-65, FU
 1300'CL GSY O, SWB .5880 NW/1ST HR,
 .4580 NW/2ND HR, AC 500, SWB & REC PT
 LD, FU 1600'O, SWB DWN & SWB AVG 2.07
 BOPH, NW/7HRS, WEEKEND/FU 1900'O, AC
 2500, SWB DWN & SWB 8.1280/1ST HR &
 6.9680/2ND HR, ON/FU 1500'FL (300' AC
 WTR), SWB DWN & SWB 5.738FPH 76%OIL/
 5HRS, T&R, POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

RECORDED
 774