

8-4

153-20,726 -00-00

6 031276

API NUMBER 15-

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW NE _____, SEC. 5, T. 4, S, R. 36
3300 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4528

Lease Name Kehlbeck Well # 3

Operator: Paul Prijatelj
Name & Address: 201 W 8th Street
Suite 409
Pueblo, Colorado 80123

County Rawlins 154.70
Well Total Depth 4760 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 366 cwc

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Ks.

Company to plug at: Hour: AM Day: 4 Month: August Year: 19 89

Plugging proposal received from Bill

(company name) Kelso (phone) _____

were: 8 5/8" set at 366' /cwc 4 1/2" set at 4746' w/250 sks. Perf 4724' - 29'.

Order sand and common cement. Pull pipe. Ordered 225 sks 65/35 poz 10% gel 500# hulls

Halliburton Cement Co. LaRue Water Trucks.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 10:40AM Day: 4 Month: August Year: 19 89

ACTUAL PLUGGING REPORT Sand bottom to 4640' w/4 sks common cement on sand w/
bailer. 5 shots from 2800'. Recovered 1800' of casing. Squeezed 8 5/8" w/225 sks
cement blend w/500# hulls mixed in to max psi 600#. Close in psi 250#. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION

AUG 14 1989 8-14-89

Remarks: _____
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED serve this plugging.

Signed Carl Goodrow
(TECHNICIAN)

Carl Goodrow

DATE 8-17-89
INV. NO. 25665