

6 030916

API NUMBER 15- 153-20,597-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NE , SEC. 5 , T 4 S, R 36 W/E
4620 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8301 8793

Lease Name Kehlbeck Well # 1-D

Operator: James Dillie Oil and Gas Ventures
Name & Address 4469 S. Winon Court
Denver, Colorado 80236

County Rawlins 154.86
Well Total Depth 4765' feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 302

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050
Address Chase, Kansas

Company to plug at: Hour: PM Day: 6 Month: 7 Year: 19 87

Plugging proposal received from Mark

(company name) Kelso Casing (phone)

were: 8 5/8 set @ 302' w/ 225 sx cwc 5 1/2 " set @ 4761 w/265 sx.

PBTD 4749' Perf. 4618 - 4703' order sand and com. cmt. shoot and pull pipe.

Order 200 sx ALT.Cmt. blend 65/35 poz 10% gel 2% Dicol 5 sx hulls Allied Cmt. Co.

LaRue Water Trucks

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:15 PM Day: 6 Month: 7 Year: 19 87

ACTUAL PLUGGING REPORT Dump sand on PBTD to 4699' w/ 5 sx com. cmt.

on sand w/bailer. One shot recovered 3033' of 5 1/2" csg.

squeezed 8 5/8 w/ 5sx hulls 200 sx ATL. cmt. blend.

Max PSI 400 # close in PSI # 200 Plug complete.

RECEIVED
STATE CORPORATION COMMISSION

JUL 16 1987 7-16-87

CONSERVATION DIVISION
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 7-20-87

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 17518

Carl Goodrow