

6030406.

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-023-20,194-00-00

CSE NWSW SEC. 34, T. 4 S, R 37 W/E

1650 feet from N/S section line

4290 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393

Lease Name Flemming Well # 1

Operator: A. L. Abercrombie Inc.

County Cheyenne 160.29

Name & Address 801 Union Center

Well Total Depth 4932 feet

Wichita, Kansas

Conductor Pipe: Size _____ feet

67202

Surface Casing: Size 8 5/8 feet 367

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor A. L. Abercrombie Inc. License Number 5393

Address as above

Company to plug at: Hour: PM Day: 27 Month: 3 Year: 19 85

Plugging proposal received from Bill Sowels

(company name) A. L. Abercrombie Inc. (phone) _____

were: 8 5/8" set @ 367' w/ 270 cf cement 4 1/2" set @ 4496 150 cf cement.

D.V. Tool set @ 2189 w/ 700 cf cement circ. Perf 3 holes 4381-90

Porosity 6% No pipe recovered - Ordered 125 cf 50/50 pg 6 1/2 gel 32 cc

30 cf gel 4 1/2" x hulls 4 1/2" w.P. Sem Cement Larue water trucks.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 PM Day: 27 Month: 3 Year: 19 85

ACTUAL PLUGGING REPORT Pumped down 4 1/2" casing w/ 4 1/2" x hulls 50 cf

Cement 15 cf gel 25 cf cement 6 cf gel 50 cf cement 4 1/2" w.P.

(Max press 500* Shut in 200* Plug Complete)

RECEIVED
STATE CORPORATION COMMISSION

APR 05 1985 4-5-85

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED
I (did / did not) observe this plugging.

DATE 4-8-85

Signed Carl Goodrow
(TECHNICIAN)

INV. NO. 7503
3-27