

6 031023

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 023-20,205 -00-00

NE SW NESEC. 28, T 4 S, R 37 W/E
3630 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8845

Lease Name Kerndt Well # 28-19

Operator: McCook Energy Inc.

County Cheyenne 154.83

Name & Address Formerly Snow Oil Co.

Well Total Depth 4764 feet

Box 745

Conductor Pipe: Size feet

McCook, Neb. 69001

Surface Casing: Size 8 5/8 feet 308

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor B. J. Titan License Number

Address Oakley, Kansas

Company to plug at: Hour: Day: 17 Month: Dec Year: 19 87

Plugging proposal received from Steve Swanson

(company name) McCook Energy (phone)

were: 8 5/8" set at 308' w/225 sks. 4 1/2" set at 4764' w/800 sks. Port collar at

3123' cwc. Perf at 4634' - 40'. Order 150 sks Thrifty Mix Cement Blend

65/35 Poz 10% Gel 2% Dical 5 sks Hulls. B. J. Titan Cement Co. LaRue Water Trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:45PM Day: 17 Month: Dec Year: 19 87

ACTUAL PLUGGING REPORT Squeezed 4 1/2" casing w/150 sks Cement Blend w/5 sks Hulls mixed

in to Max Psi 400#. Close in Psi 400#. Check backside 300# cement in slips.

Plug complete.

RECEIVED
STATE CORPORATION COMMISSION
1-18-88
JAN 18 1988

CONSERVATION DIVISION
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED ~~XXXXXX~~ Reserve this plugging.

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow

DATE 1-20-88
INV. NO. 19604