

4-032106

11-9

API Number: 15-023-20,191 0000

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

SW NE NW /4 SEC. 27, 04, 37 W  
4290 feet from S section line  
3630 feet from E section line

Operator license# 5393 Lease: Pianalto Well # 2

Operator: A.L. Abercrombie, Inc. County: Cheyenne

Address: Rt. 1 - Box 56 Well total depth 520 163.15 feet  
Great Bend, Kansas 67530 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 371 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 9 Month: November Year: 1995

Plugging proposal received from: Bill Sowles

Company: A.L. Abercrombie, Inc. Phone:

Were: Order 225 sxs 60/40 pozmix - 10% gel - 300# hulls.  
Allied Cement Company.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 29 1995  
CONSERVATION DIVISION  
WICHITA, KANSAS  
JIGN 11-29-95

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [ ], Part [ ], None [ X ]

Completed: Hour: 11:15 A.M., Day: 9, Month: November, Year: 1995

Actual plugging report: 8 5/8" set at 371' cwc with 275 sxs. 4 1/2" set at 4504' with 175sxs. P.B.T.D. 4436'. D.V. set at 3079' with cement circulated to surface. Squeezed 4 1/2" with 225 sxs. cement blend with 300# hulls mixed into Max. P.S.I. 300#. Close in P.S.I. 200#. Cement in Braden head on 8 5/8" annulus. Plug complete.

Remarks:  
Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO  
Bottom plug(in place): YES, CALC, NO Dakota plug: YES, NO  
Plugged through TUBING, CASING. Elevation: GL

INVOICED  
I did not observe the plugging.

Carl Goodrow  
(agent)

DATE NOV 30 1995  
INV. NO. 44152